



# Humber Station Comprehensive Environmental Impact Study and Management Plan

## Phase 3 - Comprehensive Implementation Plan, Monitoring Plan, and Adaptive Management Plan

Town of Caledon, Ontario

**Submitted to:**

Humber Station Village Landowners Group Inc.  
C/O Delta Urban Inc.  
8800 Dufferin Street, Suite 104  
Vaughan, ON L4K 0C5

**Submitted by:**

GEI Consultants Canada Ltd.  
Schaeffers Consulting Engineers  
Arcadis Professional Services (Canada) Inc.

October 2024

Project 1901485



IBI GROUP

**Issues and Revisions Registry**

Identification	Date	Description of Issued and/or Revision
First Submission	October 2024	



## **Statement of Conditions**

This Report / Study (the “Work”) has been prepared at the request of, and for the exclusive use of, the Humber Station Village Landowner Group, the Town of Caledon, and its affiliates (the “Intended User”). No one other than the Intended User has the right to use and rely on the Work without first obtaining the written authorization of GEI Consultants Canada Ltd. and its Owner. GEI Consultants Canada Ltd. expressly excludes liability to any party except the Intended User for any use of, and/or reliance upon, the work.

Neither possession of the Work, nor a copy of it, carries the right of publication. All copyright in the Work is reserved to GEI Consultants Canada Ltd. The Work shall not be disclosed, produced or reproduced, quoted from, or referred to, in whole or in part, or published in any manner, without the express written consent of GEI Consultants Canada Ltd., the Town of Caledon, or the Humber Station Village Landowner Group.



# Table of Contents

---

<b>Executive Summary</b>	<b>v</b>
<b>1. Introduction</b>	<b>1</b>
1.1 Background	1
1.2 Phase 1 and Phase 2 CEISMP Summary	2
1.3 Purpose of Phase 3 CEISMP	4
<b>2. Restoration and Enhancement Plan</b>	<b>5</b>
2.1 Pre-development Existing Natural Heritage System	5
2.1.1 Physical Setting	5
2.1.2 Existing Landscape Setting and Connectivity	6
2.1.3 Vegetation Communities	7
2.1.4 Wildlife Species and Habitat	8
2.2 Proposed Natural Feature Removals & Compensation Requirements	9
2.2.1 Drainage Feature Realignment Design	9
2.2.2 Wetlands and Woodlands	9
2.3 Preliminary Natural Heritage System	10
2.3.1 Terrestrial Connectivity and Landscape Scale Screening Exercise	10
2.3.2 NHS Ecological Targets	11
2.3.3 Targeted Invasive Species Mapping and Management	12
2.3.4 Compensation Design and Methodology	13
2.3.5 Targeted and Reference Vegetation Communities	14
2.4 Created Natural Heritage System Design	15
2.4.1 Retained NHS Buffers	15
2.4.2 Compensation Drainage Feature Realignment Design	15
2.4.3 Compensation Wetlands	15
2.4.3.1 Compensation Wetland Water Availability Assessment	16
2.4.3.2 Terrestrial Crayfish SWH Compensation Area	20
2.4.3.3 Redside Dace Contributing Habitat Compensation Area	21
2.4.4 Compensation Woodland	22
2.4.5 Amphibian Habitat Creation	22
2.5 Fluvial and Ecological Considerations for Stormwater Management Pond Outfall Location and Design	24
2.6 Restoration and Enhancement Plan Summary	24
<b>3. NHS Implementation Plan</b>	<b>26</b>
3.1 Implementation Considerations	26
3.2 Phased Buildout and Site Accessibility	26
3.3 Permitting Requirements to Agencies or other Parties	27
3.4 Sequencing of servicing, NHS construction and build-out	28
3.4.1 Construction and Conveyance	28
3.4.2 Dewatering Requirements	30
3.4.3 Water Table Lowering	32



3.4.4	Private Well Water Supplies and Well Decommissioning	33
3.5	Responsibilities for Implementation	33
3.6	Implementation Plan Summary	33
<b>4.</b>	<b>Long Term Monitoring Plan and Comprehensive Adaptive Management Plan</b>	<b>34</b>
<b>5.</b>	<b>Conclusions</b>	<b>35</b>

## **In-Text Tables**

---

Table 1.	Proposed Woodland and Wetland Removal and Compensation
Table 2.	Proposed Wetland Compensation and Enhancement Areas
Table 3.	Targeted Wetland Vegetation Community by Wetland Compensation/Enhancement Area
Table 4.	Compensation Wetland Vegetation Communities - Typical Hydroperiods
Table 5.	Monthly Water Balance Results – Present Day Soil Moisture Conditions
Table 6.	Water Balance Results (2041 – 2070 Soil Moisture Projected Conditions)
Table 7.	Water Balance Summary - Present Day Precipitation, Evapotranspiration, and Deficits
Table 8.	Projected Conditions Water Balance Summary (2041 - 2070 Project Precipitation, Evapotranspiration and Deficits)

## **Appendices**

---

### **Appendix A: Figures**

Figure 1.	Location of Study Area
Figure 2.	Existing Natural Heritage System
Figure 3.	Preliminary Natural Heritage System
Figure 4.	Landownership Plan
Figure 5.	Zone of Influence Map
Figure 6.	Proposed Land Use Plan

### **Appendix B: Fluvial Geomorphology Drawings**

Sheet G-02 –	Plan and Profile: Reach 2
Sheet G-03 –	Plan and Profile: Reach 3, Part 1
Sheet G-04 –	Plan and Profile: Reach 3. Part 2
Sheet G-05 –	Wetland Plans
Sheet G-06 –	Channel Details

### **Appendix C: Tables**

Table 9.	Conceptual Natural Heritage System Implementation (Phasing) Plan
Table 10.	Wildlife Construction Window
Table 11.	Long-Term Monitoring Plan and Comprehensive Adaptive Management Plan



# Executive Summary

---

This Phase 3 Comprehensive Environmental Impact Study and Management Plan (CEISMP), is focused on providing a detailed restoration plan for the preliminary Natural Heritage System (NHS), including retained natural feature buffers, compensation feature (woodland, wetland, drainage channel realignment) design and stormwater management pond outfall design. This Phase 3 report also outlines the Natural Heritage System phasing considerations from a planning, ecology, geotechnical and engineering perspective for conformity with policies and best management practices by discipline. Finally, this Phase 3 CEISMP includes a comprehensive monitoring and adaptive management plan, from pre-development throughout construction and post-development until assumption. The monitoring plan includes ecological (terrestrial and aquatic), fluvial geomorphology, hydrogeology, surface water engineering, erosion and sediment control and landscape architecture monitoring.

This restoration and enhancement plan includes the location and proposed restoration approach, based on Site Area physiography and NHS landscape connectivity for:

- Buffer planting for retained natural features;
- Compensation and enhancement (location, grading, planting) approach for:
  - Removed wetlands (0.38 ha) and creation of 1.40 ha of riparian and tableland wetland (Wetland Compensation Areas 1 thru 3 (0.82 ha) and Drainage realignment natural feature enhancement design (0.58 ha));
  - Removed woodland (0.34 ha) and creation of 0.35 ha of compensation woodland;
  - Realignment of 1,087 m of drainage feature length to create a final drainage feature length of 1,438 m;
  - Terrestrial Crayfish habitat removal associated with partial wetland removal (wetland compensation area 2);
  - Breeding amphibian habitat (species) removal associated with wetland removal;
  - Partial contributing Redside Dace habitat removal associated with portions of HDF-8 and HDFs 4a,10a, 11a, 12a, 13a, and 15a; and
- Fluvial and ecological considerations for stormwater management pond outfall design.

The Preliminary NHS consists of one north-south corridor (Clarkway Drive Tributary), enhanced connectivity north-south (through the Realigned Drainage Feature), and a new west-east corridor (Wetland Compensation Area 2 connecting Clarkway Tributary to Existing Woodland 2; Conceptual Wetland Compensation Area 3 connects to the Clarkway Drive Tributary; **Figure 3, Appendix A**). Ecological targets for the Preliminary NHS (retained/created features) are provided, intending to be incorporated and implemented in future planning submissions (i.e., Site Plan Application).



The Humber Station Employment Area NHS and development plan is to be built out in multiple stages with the bulk of the Prologis Site and NHS construction occurring first. A landownership Plan is included for reference in reviewing the Phased development buildout and responsible parties for implementing the development areas and the preliminary NHS (**Figure 4, Appendix A**). The Implementation Plan of this Phase 3 report summarizes the engineering, ecology and hydrogeology buildout considerations including construction and conveyance processes, and municipal and agency permitting requirements. An NHS implementation phasing plan (**Table 9, Appendix C**) and wildlife construction window (**Table 10, Appendix C**) are provided.

Lastly, **Table 11 (Appendix C)** of the Phase 3 CEISMP provides a proposed long-term monitoring plan (baseline, during construction, post-construction) and comprehensive adaptive management plan for each discipline (ecology, hydrology, hydrogeology).

The intent of the Phase 3 CEISMP, as follows, is to address the items noted above and ensure they align with the goals for the NHS for the Humber Station Employment Area and has been prepared in alignment with the approved Humber Station Village Comprehensive Environmental Impact Study and Management Plan Terms of Reference (approved August 2022).



# 1. Introduction

---

## 1.1 Background

GEI Consultants Canada Ltd. (GEI), Schaeffers Consulting Engineers, and Arcadis Professional Services (Canada) Inc., have been retained by the Humber Station Village Landowners Group Inc., to prepare the Phase 1, 2 and 3 Comprehensive Environmental Impact Study and Management Plan (CEISMP), for the Option 6 lands (herein referred to as the Humber Station Employment Area) located in Bolton, Ontario. The Humber Station Employment Area (Study Area) is generally bound by Mayfield Road to the south, Humber Station Road to the west, a tributary of the West Humber River (referred to as the Clarkway Drive Tributary) to the east and Healey Road to the north (refer to **Figure 1, Appendix A**). The Study Area is approximately 236 ha in area and is legally described as Lots 1-5, Concession 5 (Albion). It is in the West Humber watershed, within the jurisdiction of Toronto Region Conservation Authority (TRCA).

The Phased CEISMP is being completed to support an amendment to the Town of Caledon's Official Plan, to establish a Secondary Plan land use and policy framework for the Study Area (**Figure 6, Appendix A**).

The current Peel Region Official Plan (2022) identifies the lands as part of the Urban System, within the Bolton Residential Expansion Settlement Area. The Peel Region Official Plan designates the Study Area as an Employment Area.

Under the Town of Caledon Official Plan (2018), the Study Area is located within the Bolton Settlement Area and is designated as New Employment Area. In addition, HDF-3 and its associated pond, the Clarkway Drive Tributary and the northern Woodland 1 are identified as Environmental Policy Areas (EPA).

In 2023, OPA 274 was approved which outlined that Secondary Plan requirements are to be inclusive of a local Subwatershed Study (SWS) or a CEISMP, in accordance with an approved Terms of Reference by the Town of Caledon. The Terms of Reference for this CEISMP was submitted to the TRCA and the Town in January 2022 and approved in August 2022; a copy of this is included in the Phase 1 CEISMP report (Appendix B1). Like a SWS, the CEISMP is a comprehensive planning framework describing how a wide range of development elements will be addressed. This includes the following three phases of reporting:

- Phase 1: Provide characterization of existing environmental condition, address the relevant natural features and functions identified in the PPS, Region of Peel Official Plan, and Town of Caledon Official Plan; and provide the foundation for the layout of the Secondary Plan by defining and delineating elements such as the NHS and transportation and servicing networks;
- Phase 2: Detailed analysis, impact assessment, mitigation, and recommendations based on the findings from Phase 1 and the proposed Land Use Concept; and
- Phase 3: Implementation plan, monitoring plan, and adaptive management plan based on the findings from Phase 2.





The first submission of the Phase 1 CEISMP was made in October 2023, with a second submission submitted in July 2024. This October 2024 submission of the Phase 3 CEISMP was made concurrently with the 1st submission of the Phase 2 CEISMP.

## 1.2 Phase 1 and Phase 2 CEISMP Summary

As documented in the Phase 1 CEISMP, the Study Area is comprised mainly of actively cultivated fields with most of the natural and cultural vegetation in the east valley, which surrounds a tributary of the West Humber River. One large woodlot (8.09 ha) occurs on the tableland in the north-west corner of the Study Area, and a second smaller woodlot (1.20 ha) is in the north-central portion. The remainder of vegetation communities on the tableland are small and isolated non-treed wetlands and cultural vegetation communities (**Figures 1 and 2, Appendix A**). Scattered residential dwellings also occur in the Study Area, fronting onto the bordering roads. A tributary of the West Humber River (the Clarkway Drive Tributary) provides direct warm water fish habitat and flows in a north-south direction at the east end of the Study Area and generally occurs within a defined valley. Headwater Drainage Feature HDF-3 also provides seasonal warm water fish habitat, and flows in a north-south direction at the north central and west end of the Study Area.

As part of the Phase 1 CEISMP, GEI completed field investigations in 2017, 2018, 2021, 2022, and 2023 to achieve a fulsome understanding of the ecological conditions within the Study Area, and to address specific requests for targeted surveys from the Toronto and Region Conservation Authority (TRCA). As outlined in the approved Terms of Reference (attached as Appendix B1 in the Phase 1 CEISMP), Phase 1 of the CEISMP characterizes existing conditions, demonstrates a baseline inventory and provides a cross-synthesis of the various disciplines. As part of the Phase 1 CEISMP the following significant natural heritage features were identified:

- Significant wetlands;
- Significant woodland;
- Fish habitat;
- Significant wildlife habitat:
  - Seasonal Concentration Areas of Animals (Candidate Bat Maternity Colonies within FOD habitats);
  - Specialized Wildlife Habitat (Candidate Seeps and Spring);
  - Species of Conservation Concern (Terrestrial Crayfish, Snapping Turtle (*Chelydra serpentina*), Eastern Wood Peewee (*Contopus virens*), Monarch (*Danaus plexippus*), and Yellow-banded Bumblebee (*Bombus terricola*)); and
- Habitat of endangered and threatened species (Bank Swallow (*Riparia riparia*) foraging habitat and Redside Dace (*Clinostomus elongatus*) contributing habitat).

Additional natural heritage features within the Study Area included evaluated non-significant wetlands and other woodlands.

The Phase 2 CEISMP is submitted concurrently with this Phase 3 CEISMP. Phase 2 CEISMP is focused on natural heritage features and functions and impact assessment and mitigation of the proposed development.



The components of the Phase 2 CEISMP include an assessment of potential impacts of the land use plan on natural heritage features and functions, and groundwater and surface water systems, including:

- Terrestrial and aquatic impacts, including recommendations for the avoidance, minimizing and/or mitigation of potential impacts to these features;
- Preliminary assessment of compensation efforts for proposed feature removals and realignment;
- Impacts to geotechnical conditions and slope stability;
- Impacts to local groundwater resources, groundwater supported features, and recommendations for mitigation measures;
- Hydrologic, floodplain and regional storm impacts;
- Geomorphic assessments and erosion sensitivity analyses;
- Servicing and grading impacts;
- Stormwater management plans and SWM pond design;
- A brief description of natural heritage mitigation and restoration opportunities; and
- Recommended mitigative measures and best management practices from each discipline.

Through the Phase 2 CEISMP report, the above impacts were contemplated and assessed in alignment with relevant legislation, policies and regulations. To ensure alignment with the Town of Caledon Official Plan (2018) the Phase 2 CEISMP was prepared in conjunction with the Humber Station Employment Area Secondary Plan policies, which were revised to address specific environmental conditions for the preliminary NHS. This includes a proposed amendment to the Town of Caledon's Official Plan (2018) to modify how Core Woodland Areas can be addressed during planning applications as follows:

*7.16.7.3. The limits of wetlands, woodlands, and stream corridors within the Secondary Plan Area are established through the recommendations of the CEISMP and form the basis for the Environmental Policy Area designation. The recommendations of the CEISMP may include minor modifications (i.e. encroachment/removal and appropriate compensation) of Woodland Core Areas, which may be permitted through an approved Environmental Management Plan (in accordance with 5.7.3.1.2). Development and site alteration will not be permitted within this designation except as set out in the CEISMP.*

It is assumed that upon approval of the secondary plan policies submitted as part of the OPA for this Secondary Plan area, that the preliminary NHS will proceed to include minor compensation and enhancement of the Core Areas; the details of this compensation are included in this report and will be further detailed through an Environmental Management Plan (EMP) as required.

The results of the Phase 2 CEISMP are further addressed through this Phase 3 report to address the implementation of the preliminary NHS, inclusive of retained features, compensation areas, restoration and enhancement areas, and vegetated protection zones (VPZs).



### **1.3 Purpose of Phase 3 CEISMP**

As noted earlier, this Phase 3 CEISMP is focused on providing a detailed restoration plan for the preliminary Natural Heritage System, including retained natural feature buffers, compensation feature (woodland, wetland, drainage channel realignment) design and stormwater management pond outfall design. This Phase 3 report also outlines the NHS phasing considerations from a planning, ecology, geotechnical and engineering perspective for conformity with policies and best management practices by discipline. Finally, this Phase 3 CEISMP includes a comprehensive monitoring and adaptive management plan, from pre-development throughout construction and post-development until assumption. The monitoring plan includes ecological (terrestrial, aquatic), fluvial geomorphology, hydrogeology, surface water engineering, erosion and sediment control and landscape architecture monitoring.



## 2. Restoration and Enhancement Plan

---

This restoration and enhancement plan, based on the impact assessment and recommendations from the Phase 2 CEISMP and Humber Station Employment Area Secondary Plan policies includes:

- Buffer planting approach for retained natural features;
- Compensation (location, grading, planting) approach for:
  - Removed wetlands (0.38 ha);
  - Removed woodland (0.34 ha);
  - Realignment of 1,087 m of drainage feature length;
  - Terrestrial Crayfish habitat removal associated with partial wetland removal;
  - Breeding amphibian habitat removal (species) associated with wetland removal;
  - Partial contributing Redside Dace habitat removal associated with portions of HDF-8 and HDFs 4a, 10a, 11a, 12a, 13a, and 15a; and
  - Fluvial and ecological considerations for stormwater management pond outfall design.

A restoration and enhancement plan are prescribed in the sections below, informed by physiography, surficial geology, retained native communities in the Study Area and natural heritage system landscape connectivity within and adjacent to the Study Area.

### 2.1 Pre-development Existing Natural Heritage System

#### 2.1.1 Physical Setting

The uppermost mapped bedrock unit underlying the Study Area is the Upper Ordovician Georgian Bay Formation (Ontario Geological Survey, 2005). The Georgian Bay Formation consists of dark blue grey to black shale with interbeds of limestone (Ontario Geological Survey, 2005). The mapped surficial Quaternary deposits at the Study Area consist predominantly of clayey silt till with shale and siltstone clasts. This till unit has been interpreted to be the Halton Till. As identified in the “Soil Survey of Peel County” (Hoffman and Richards, 1953), soils in this area were derived from parent materials of lacustrine soil over clay till or heavy textured till with imperfect drainage. The Peel clay member and / or Monaghan clay loam covers much of the Bolton area. The Peel clay member generally corresponds to areas of glaciolacustrine deposits, and the Monaghan clay loam corresponds to the area of surficial till (Hoffman and Richards, 1953). The soils mapping and Quaternary geology mapping are generally consistent.

The regional topography of the Study Area generally slopes in a southeasterly direction. Ground elevations at the Study Area range from about 245 metres above sea level (masl) in the northern portion of the Study Area to approximately 230 masl in the southern portion of the Study Area. Regional drainage is generally directed to the south/southeast into the



Humber River, and eventually into Lake Ontario. There is an incised tributary of the West Humber River that trends in a north south direction along the eastern subject area boundary, referred to as the Clarkway Drive Tributary. In addition, two other incised headwater feature drainages occur within the Study Area; HDF-8 and HDF-3 (**Figure 2, Appendix A**).

### **2.1.2 Existing Landscape Setting and Connectivity**

The Study Area is unique as it spans a portion of both Ecoregion 6E and 7E. The southern fifth of the Study Area is located within Ecoregion 7E (specifically eco-district 7E-4), while the remainder of the Study Area is located within Ecoregion 6E (specifically eco-district 6E-7). Ecoregion 7E is located within the Carolinian, or Deciduous Forest Zone (also referred to as the mixed wood plains), an area characterized by a relatively warmer climate, which supports plant species typical of more southern areas. Broadleaved trees, including American Beech (*Fagus grandifolia*), Sugar Maple (*Acer saccharum*), Basswood (*Tilia americana*), Red Maple (*Acer rubrum*), White Oak (*Quercus alba*) and Bur Oak (*Quercus macrocarpa*), dominate natural upland forest cover in this region (Rowe, 1972). Also found in this region are Canada's main distribution of Black Walnut, Sycamore, Swamp White Oak (*Quercus bicolor*) and Shagbark Hickory (*Carya ovata*). However, a majority of the Study Area is located within the Lake Simcoe-Rideau Ecoregion 6E, which extends from Lake Huron to the Ottawa River, and includes most of the Lake Ontario shore and the Ontario portion of the St. Lawrence River Valley. Ecoregion 6E falls within the Great Lakes-St. Lawrence forest region, an area of moderate climate where natural succession leads to forests of shade tolerant hardwood species including Sugar Maple, American Beech and shade intermediate species such as Red Oak (*Quercus rubra*) and Yellow Birch (*Betula alleghaniensis*), as well as associations of White Pine (*Pinus strobus*) and Red Pine (*Pinus resinosa*).

Consideration of the larger ecological matrix or landscape contributes to a better understanding of potential interactions between abiotic and biotic flows and exchanges. No ANSIs or ESAs are identified within 120 m of the Study Area. As depicted on **Figure 2 (Appendix A)**, the landscape surrounding the Study Area is dominated by agricultural fields. Under existing conditions there is one north-south corridor associated with the Clarkway Drive Tributary which ultimately feeds into the West Humber River. The Clarkway Tributary (4.7 m in average width) is comprised of upland and wetland vegetation communities, and non-woody and woody vegetation types. The Clarkway Tributary likely provides a corridor function for terrestrial, semi-aquatic and aquatic flora and fauna. North of Bolton, the corridor leads to a large continuous forest in the Humber River valley. South of Mayfield Road, the Clarkway Tributary continues through agricultural fields and residential developments before joining at Claireville Conservation Area. Based on the criteria provided by Peel-Caledon Significant Wildlife Habitat Study (North-South Environmental Inc. *et al.* 2009) the Clarkway Drive Tributary and its associated valleyland may be considered a regional movement corridor as the natural features connected cross active agricultural lands within the landscape.

Other primary wildlife linkage corridors found near the Study Area may include the Greenbelt Protected Countryside corridor west of the Study Area. This feature affords a larger naturalized area that may provide additional cover and refuge for wildlife. Continuous forest



cover protects wildlife while they are foraging, migrating, mating and/or overwintering from predators and human-intervention. Larger mammals can range over larger areas in response to seasonal behaviours and requirements. Typically, wildlife will follow traditional migration routes or corridors (OMNR 2000). These two wildlife corridors (i.e., the Clarkway Drive Tributary and the Greenbelt Protected Countryside) are generally impeded by the existing road network around the greater Study Area which serves as a barrier to wildlife movement due to busy roads. Specifically, Mayfield Road is a major arterial roadway for Caledon and Brampton. With increased densification projected within the Bolton Area, it is anticipated that all surrounding roadways including Humber Station Road (to the west), and Healy Road (to the north) will become busier and will pose an increased risk to wildlife movement. No suitable wildlife passage opportunities (e.g., culverts) were documented during ecological inventories.

### **2.1.3 Vegetation Communities**

The Study Area is dominated by actively cultivated fields, with natural features generally associated with the Clarkway Drive Tributary, and several forest and wetland communities (**Figure 2, Appendix A**).

Within the Study Area, several wetlands were determined to be assumed or confirmed Significant Wetlands (PSW). Confirmed and assumed PSWs (the majority of which are off-site) are associated with the Clarkway Drive Tributary and the confirmed PSW is located at the downstream extent of HDF-3. The Deciduous Forest (FOD) within a non-participating property in the north and the Fresh – Moist Basswood Deciduous Forest (FOD8-3) complexed with the adjacent CUT1-7 communities within the north central portion of the Study Area are also considered Significant Woodlands.

- Nine locally (Peel Region, TRCA) rare plants were observed, as per the rankings of Varga et al. (2005) and TRCA (2021). The locally rare species were:
  - White Spruce (*Picea glauca*) – planted;
  - Tall Beggarticks (*Bidens vulgata*) – occasional at edges of meadows along the tributary;
  - Marsh Seedbox (*Ludwigia palustris*) – occasional in MAM2-2;
  - Pennsylvania Smartweed (*Persicaria pensylvanica*) – occasional on the shore of SAS1-1;
  - Catchweed Bedstraw (*Galium aparine*) – occasional in unit FOD8-3;
  - Peach-leaved Willow (*Salix amygdaloides*) – local along the tributary, drainages, and SAS1-1;
  - Sandbar Willow (*Salix interior*) – local along the tributary, drainages, and SAS1-1;
  - Small's Spike-rush (*Eleocharis palustris*) – local in MAM2-2 and along exposed banks of the tributary; and
  - Small Pondweed (*Potamogeton pusillus*) – common in SAS1-1.
- Depending on the timing of wetland removal and wetland compensation construction, opportunities to salvage individual rare species should be assessed in future planning stages.



### 2.1.4 Wildlife Species and Habitat

The following SAR were observed during wildlife surveys within the Study Area:

- Eastern Wood-Pewee (*Contopus virens*; Special Concern in Ontario and Canada) identified within the northwestern FOD community in a non-participating property;
- Snapping Turtle (*Chelydra serpentina*; Special Concern in Ontario and Canada) observed in SAS1-1 associated with HDF-3 and within the Clarkway Tributary;
- Monarch (*Danaus plexippus*; Special Concern in Ontario and Endangered in Canada) observed in old field/meadow locations associated with the Clarkway Drive tributary;
- Yellow-banded Bumble Bee (*Bombus terricola*; Special Concern in Ontario and Canada) observed in old field/meadow and wetland locations associated with the Clarkway Drive tributary;
- Barn Swallow (*Hirundo rusica*; Special Concern in Ontario and Canada) nesting habitat occurs in two replacement structures that were installed in 2017, and have been observed foraging off-site over the PSW associated with the northern portion of the Clarkway Drive Tributary; and
- Bank Swallow (*Riparia riparia*; Threatened in Ontario and Canada) foraging habitat observed off-site over the PSW associated with the northern portion of the Clarkway Drive Tributary.

In addition, the Clarkway Drive Tributary provides direct fish habitat and HDF-3 provide seasonal warm water fish habitat. The Clarkway Drive Tributary and its riparian wetlands, as well as HDFs 4a, 8a, 8a1, 8a2, 8a3, 8b, 8c, 8c-2, 8d, 10a, 11a, 12a, 13a, and 15a provide contributing habitat for Redside Dace.

Within the Study Area, the following Significant Wildlife Habitat types are present:

- Seasonal Concentration Areas of Animals:
  - Candidate Bat Maternity Colonies within northwestern FOD community in a non-participating property.
- Specialized Wildlife Habitat:
  - Candidate Seeps and Spring within northwestern FOD community in a non-participating property and southeast FOD7-6 community located in non-participating properties.
- Species of Conservation Concern:
  - Terrestrial Crayfish (MAM2-2 associated with HDF-3, MAS2/MAM2, MAM2-10/MAM2-2, MAS2, MAS2-1 communities associated with the Clarkway Drive tributary);
  - Snapping Turtle (SAS1-1, Clarkway Drive tributary);
  - Eastern Wood Peewee (FOD);
  - Monarch (MAM2-10/MAM2-2 and MAS2-1 communities associated with the Clarkway Drive tributary); and
  - Yellow-banded Bumblebee (MAM2-10/MAM2-2 and MAS2-1 communities associated with the Clarkway Drive tributary).



## 2.2 Proposed Natural Feature Removals & Compensation Requirements

### 2.2.1 Drainage Feature Realignment Design

Within the Study Area, portions of HDF-3 are proposed for realignment from Healey Road within a non-participating property to the agricultural pond (SAS1-1) and surrounding SWT2-2 community. The proposed realignment will result in the removal of 1,087 m of channel but creates 1,438 m of channel length, representing a net gain of 351 m (**Figure 3, Appendix A**).

HDF-3 is identified as providing seasonal fish habitat. The natural drainage feature realignment is anticipated to provide an overall ecological benefit by improving water quality and riparian vegetation compared to the existing drainage which has been historically straightened and degraded by ongoing agricultural management resulting in siltation from ploughing to the edge of the feature, and pollution from fertilizers. This drainage feature realignment will undergo a natural channel design that incorporates native riparian vegetation and floodplain wetlands (online and offline) to support surface water storage along the feature. The proposed drainage feature realignment is anticipated to provide improved fish habitat compared to existing conditions. It will also provide connectivity between other features within the preliminary NHS including retained and compensation woodlands and wetlands.

Portions of HDF-8 (8a1, 8a2, and 8a3 are to be retained), and HDFs 4a, 10a, 11a, 12a, 13a, and 15a are considered contributing Redside Dace habitat and are proposed for removal. As such, compensation is required to ensure the form and function of this contributing habitat is replicated and enhanced through the design of SWM Ponds 1 and 3, as well as the creation of wetland compensation habitat (Wetland Compensation Area 3). Similar to HDF-3, these features are currently disturbed and degraded due to active agricultural practices causing siltation due to ploughing and pollution from fertilizers. As such removal and replication in an enhanced state is anticipated to provide a net gain.

### 2.2.2 Wetlands and Woodlands

As described in the Phase 2 CEISMP, 0.34 ha of woodland and 0.38 ha of wetland are proposed for removal and compensation (**Table 1**). This Phase 3 CEISMP provides the ecological design for woodland (0.35 ha) and wetland (1.40) compensation and enhancement. The proposed realigned drainage channel provides offline and online wetland compensation and wetland enhancement areas (Wetland Compensation Area 1 and Drainage Realignment Enhancement Area), the extended floodplain of the proposed realigned drainage channel provides online wetland compensation (Wetland Compensation Area 2) and tableland wetland compensation is also provided (Wetland Compensation Area 3), to be hydrologically supported by roof drainage and precipitation inputs (**Tables 1-2; Figure 3, Appendix A**).





**Table 1: Proposed Woodland and Wetland Removal and Compensation**

Feature Type	Removed (ha)	Compensation (ha)	Enhancement (ha)	Net Gain (ha)
Woodland	0.34	0.35	N/A	+ 0.01 ha
Wetland	0.38	0.82 (inclusive of RSD contributing habitat compensation wetland)	0.58	+1.02 ha

**Table 2: Proposed Wetland Compensation and Enhancement Areas**

Compensation Wetland Number	Riparian Wetland (ha)	Tableland Wetland (ha)	Total Area (ha)
Drainage Feature Enhancement	0.58	N/A	0.58
Compensation Area 1	0.077	N/A	0.077
Compensation Area 2	0.39	N/A	0.39
Compensation Area 3	N/A	0.35	0.35
TOTAL	1.05	0.35	1.40

## 2.3 Preliminary Natural Heritage System

The preliminary Natural Heritage System is comprised of significant natural heritage features and functions and their buffers as identified through the Phase 1 and Phase 2 CEISMP; it also includes created compensation natural features as identified in the Phase 2 CEISMP and detailed within this Phase 3 CEISMP (**Figure 3, Appendix A**).

The compensation features (woodland and wetlands) and drainage feature wetland enhancements will support a more robust Natural Heritage System, including increased connectivity between the new and retained natural features (**Figure 3, Appendix A**).

This Phase 3 CEISMP provides ecological targets for the preliminary NHS, summarizes applicable policies and best practices for retained natural feature buffers and created natural features and includes conceptual compensation design (natural channel, wetlands, woodland), including hydraulic analysis, water availability assessment and targeted vegetation communities.

### 2.3.1 Terrestrial Connectivity and Landscape Scale Screening Exercise

Under pre-development conditions there is one north-south corridor (**Figure 2, Appendix A**) associated with the Clarkway Drive Tributary valley which enters the Study Area from the north-east and exits the Study Area at Mayfield Road.



The proposed preliminary NHS (**Figure 3, Appendix A**) is designed to maintain this north-south corridor and proposes additional opportunities for connectivity between retained, compensation, and enhancement features within the Study Area. The preliminary NHS proposes an east-west connection between the realigned drainage channel (HDF-3) and retained Woodland 2/Wetland C1 to the Clarkway Drive Tributary valley. This new NHS connection will be approximately 60 m wide and will connect the retained upland Significant Woodland (FOD8-3) to the realigned drainage channel to Wetland Compensation Area 2 and the Woodland Compensation Area, to the upland setback of the Clarkway Drive Tributary.

A wide diversity of habitats are provided along this new east-west corridor including upland woodlands, a riparian channel with online (shallow marsh) and offline (meadow marsh) wetlands within the floodplain, the vegetated setback of the Clarkway Drive Tributary, and the Tributary itself. This east-west corridor allows for flora and fauna gene flow between the north-south corridor associated with the Clarkway Drive Tributary.

HDF-3 is proposed to be enhanced through the realignment and naturalization process and will provide increased north-south connectivity.

The proposed NHS also includes a 20 m wide east-west connection between the Clarkway Tributary through the conceptual wetland compensation area 3.

### **2.3.2 NHS Ecological Targets**

The following NHS ecological targets are proposed:

- Create a dynamic stable realigned drainage feature that will naturally evolve over time;
- Provide natural vegetative cover across the entire created NHS and all NHS buffers;
- Achieve an overall measurable net gain in native vegetation community types and species diversity (flora and fauna);
- Create breeding, summer use and overwintering habitat for American Toad (*Anaxyrus americanus*), Northern Leopard Frog (*Lithobates pipiens*), Green Frog (*Rana clamitans*) and Gray Tree Frog (*Dryophytes versicolor*);
- Create improved habitat through compensation efforts for Terrestrial Crayfish (SWH) and Redside Dace (contributing habitat);
- Provide habitat for certain life stages of various bird and small and medium sized mammal species;
- Mitigate removal of wetlands and woodland by providing appropriate areas for compensation and by increasing ecological functions within created wetland and woodland features;
- Map abundance of Category 1 invasive species (i.e., *Rhamnus cathartica*, *Phragmites australis* ssp. *australis*) and *Populus alba* (Category 2) within retained natural features;
- Invasive species management (risk) assessment to determine whether it is ecologically, socially, and economically viable to manage a given invasive species population;



- Where invasive species risk assessment identifies invasive management, for a given species, carry out invasive management as per Ontario Invasive Plant Council (OIPC) best management practices (OIPC, 2024);
- Proper disposal of invasive species (i.e., Phragmites), that are within development area as per OIPC best management practice (OIPC, 2024);
- Explore salvage and transplant of native species within removed features into created features and or retained feature buffers, where feasible;
- Enhance local linkages and connectivity for wildlife movement and gene flow; and
- Consider best management practices for road crossings, if necessary, to support movement of amphibians, reptiles, small and medium sized mammals under road crossings.

It is expected that future planning applications (i.e., draft plan of subdivision and site plan application) will adhere to and implement these NHS ecological targets.

### **2.3.3 Targeted Invasive Species Mapping and Management**

At the planning submission that follows the CEISMP (i.e. Draft Plan of Subdivision or Site Plan Application) it is expected that the abundance of Category 1 invasive species (i.e., *Rhamnus cathartica*, *Phragmites australis* ssp. *australis*) and *Populus alba* (Category 2) within retained natural features will be mapped and an invasive management plan developed.

Prioritization is required as part of the invasive species management assessment to determine whether it is ecologically, socially, and economically viable to manage a given invasive species population. Generally, the risk assessment focuses on: (a) whether the species can be reasonably eradicated or contained and (b) the risk that the species poses to high-quality retained features in the vicinity.

Species-specific invasive species management strategies should consider multiple variables when determining whether active management is warranted (i.e., using chemical, biological, or physical interventions) or whether indirect management is appropriate (i.e., supporting natural succession). These variables include species' biological traits, proximity to dispersal routes and rare or sensitive features (i.e., significant natural heritage features, Species at Risk), impairment to recreational opportunities, practicality of control efforts, and likelihood of re-invasion from off-site (where management is not possible). The prioritization process segregates high priority from lower priority invasive occurrences and helps define management approaches. High priority areas for invasive species treatment are where the greatest potential exists to eradicate the invasive species, protect Species at Risk that are of highest concern, and manage invasive species that require the least amount of labour investment.

Where the risk assessment identifies that active management is warranted, the management level that can be reasonably achieved must be determined. There are five management levels:

- Eradicate;
- Eradicate/Contain;



- Contain;
- Control; and
- Follow-up.

Eradication aims to target invasive species having smaller, more localized populations. Eradicate/contain should be viewed as ‘eradicate, if possible, but contain if eradication is not feasible based on existing conditions. Containing an invasive species is an approach intended to cordon widespread plants into isolated sites by removing or treating thinner populations/outlying specimens. The goal is to slow the rate of spread and contain the core population. Efforts to contain an invasive species must continue indefinitely unless the feasibility of eradicating the core occurrence changes. Control (sometimes referred to as asset-based protection) means strategically choosing specific locations within an invasive population where control efforts will be undertaken. This approach is typically reserved for the most invasive species that occupy significant areas and threaten high-value features, such as Species at Risk (Sherman 2015; U.S. Fish and Wildlife Service et al. 2018). If historical records indicate the occurrence had been removed or treated, it should be placed into the category of “follow-up” – indicating additional surveys should be conducted to determine if the species has re-established and, if so, the percent cover of the species within the native habitat. Of note, the significant woodland for which a minor removal and compensation has been proposed (Woodland 2; **Figure 3, Appendix A**), is comprised of both native FOD8-3\* forest, and CUT comprised mostly of Common Buckthorn (*Rhamnus cathartica*). To support the Phase 2 CEISMPs recommendations for improving the ecological integrity of the retained feature this area is recommended that an Environmental Management Plan (EMP) be developed and include priority invasive species eradication to support restoration of the native habitat.

### **2.3.4 Compensation Design and Methodology**

The following policies and best management practices informed the restoration and enhancement plan:

- Erosion and Sediment Control Guideline for Urban Construction (Toronto and Region Conservation Authority, 2019);
- Guideline for Determining Ecosystem Compensation (Toronto and Region Conservation Authority, June 2023);
- Post-Construction Restoration Guidelines (Toronto and Region Conservation Authority, July 2004). This guideline applies to the FOD8-3 which is proposed for partial removed;
- Preserving and Restoring Healthy Soil: Best Practices for Urban Construction, (Toronto and Region Conservation Authority, June 2012);
- Seed Mix Guidelines (Toronto and Region Conservation Authority, January 2022);
- Town of Caledon OP (2018) Environmental Policy Area provisions for the Coleraine West Employment Area Land Use Plan (Section 7.15.8(iv));
- Humber Station Employment Area Land Use Plan (SGL Planning, 2024 – submitted as part of the OPA process for the Study Area); and
- International principles and standards for the practice of ecological restoration. Second edition. Restoration Ecology S1-S46 (Gann et al. 2019).



### **2.3.5 Targeted and Reference Vegetation Communities**

The design process of restoring or creating ecosystems depends on the use of native reference sites to inform restoration activities (Gann et al., 2019). Reference sites are defined as ecosystems that have experienced little to no human intervention or disturbance, and that are as close to historically natural as possible (Pollock et al., 2012). In the discipline of ecosystem restoration, reference sites are a vital tool for assessing current conditions and developing restoration goals for natural areas (Gann et al., 2019). They are used to inform scientists of the best management practices to lead to a healthy recovery of a degraded ecosystem, and they can also be used to assess whether current management practices are moving the restoration of a site in the direction of recovery (Pollock et al., 2012).

To be used as a reference site, proposed locations must have specific characteristics. To assist ecologists in identifying appropriate reference sites, The Society for Ecological Restoration (SER) has outlined six essential reference site attributes. These attributes include: 1) absence of threats, 2) suitable physical conditions, 3) appropriate species composition, 4) ample structural diversity, 5) adequate ecosystem function, and 6) sufficient external exchanges (Gann et al., 2019).

In Southern Ontario, there are few reference sites that meet the six reference site attributes as the natural environment was highly altered >200 years ago, primarily from the removal of woodlands and other natural habitat types for agricultural practices. This is also true for Caledon and the surrounding landscape, which can be described as containing lands heavily influenced by anthropogenic activities. When appropriate reference sites cannot be determined for a restoration project, Certified Ecological Restoration Practitioners (CERPs) will use target ecosystems as an alternative. While reference sites are physical locations where data has been collected and it has been determined that the SER's reference site attributes are adequately met, target ecosystems are conceptual descriptions of community assemblages, such as those found in the ELC manual (Lee et al. 1998). The target ecosystem method leaves more to the discretion of the CERP; however, since the community descriptions in the ELC manual are based on data collected from actual sites within Ontario, these descriptions should serve as a fair alternative to reference sites when necessary.

#### ***Physiographic Considerations***

When selecting reference sites and target ecosystems CERPs must consider the physiographic conditions of the area to be restored. This approach ensures the greatest likelihood of success for communities that have been restored on the landscape.

As previously stated in **Section 2.1**, the Study Area is situated in the Peel Plain physiographic region. The soil texture present within the Clarkway Tributary is a clay to silt texture. The primary soil texture will inform the design of restoration vegetation communities.



## 2.4 Created Natural Heritage System Design

### 2.4.1 Retained NHS Buffers

The Phase 2 CEISMP identified providing 10 m buffers from Significant Woodland, 10 m buffers from local wetland and 30 m buffers from significant wetland. The natural feature buffers should be planted with native vegetation that are suitable based on soil texture, soil moisture, aspect and topography. Buffer plantings should consider the need for protection from sunscald and windthrow (treed communities) and for barrier planting to deter future residents from creating their own trails into the natural features.

### 2.4.2 Compensation Drainage Feature Realignment Design

The complete drainage feature realignment design is shown in **Appendix B** (Sheets G-01 through G-04, with channel details shown in G-06). The proposed design is also outlined in the Phase 2 CEISMP. The design creates a riffle-pool morphology to provide enhancements to aquatic habitat, provides connections between retained wetlands, and creates additional wetland habitat within the floodplain, which will receive flows from the channel at higher flows. It is anticipated that the slopes for this feature realignment will be planted with native shrubs and grasses, and any wetland design will follow the methods outlined below.

### 2.4.3 Compensation Wetlands

Three wetland compensation areas are planned (**Figure 3, Appendix A**). Compensation Area 1 is within the realigned drainage channel, Compensation Area 2 is a created extended floodplain from the realigned drainage channel and Compensation Area 3 is a tableland wetland hydrologically supported by precipitation and a roof drain collector system. The detailed wetland design is shown in (**Appendix B, Drawing G-05**).

Three wetland native vegetative communities are targeted for compensation (Table 3):

- Willow Thicket Swamp (SWT2-2) communities consist of <25% tree cover and >25% shrub cover. Dominated by hydrophytic tree and shrub species. Surface water inundation is >30% of ground coverage for part of the year. This vegetation type is targeted for the offline wetlands within the drainage realignment enhancement areas and Wetland Compensation Area 1.
- Mineral shallow marsh (MAS) communities consist of less than 25% cover of trees and shrubs with a hydrophytic emergent macrophyte cover greater than 25%. Water is expected to be standing through most of the growing season and substrates can range from bedrock to mineral to organic. This vegetation type is targeted for online wetlands within the proposed drainage realignment) and within Wetland Compensation Areas 2 and 3.
- Mineral Meadow Marsh (MAM2): Mineral soils seasonally flooded that later become moist to dry, features dominated by grasses/sedges intolerant to prolonged flooding, less than 25% cover of both emergent vegetation and trees/shrub. This vegetation type is targeted for offline wetlands within the proposed drainage realignment area, Wetland Compensation Area 2 and Wetland Compensation Area 3.



**Table 3 - Targeted Wetland Vegetation Community by Wetland Compensation/ Enhancement Area**

Targeted Wetland Vegetation Community	Drainage Realignment Enhancement Wetlands and Wetland Compensation Area 1 – Riparian Offline Wetlands	Drainage Realignment Enhancement Wetlands – Riparian Online Wetlands	Wetland Compensation Area 2	Wetland Compensation Area 3
Willow Thicket Swamp	Yes	No	No	No
Mineral Shallow Marsh	No	Yes	Yes	Yes
Mineral Meadow Marsh	Yes	No	Yes	Yes

2.4.3.1 Compensation Wetland Water Availability Assessment

A critical component of designing wetlands is to determine whether appropriate water balances can be maintained post-development to ensure features continue to function properly; the typical hydroperiods for the proposed wetland compensation types can be seen in **Table 4**.

**Table 4 - Compensation Wetland Vegetation Communities - Typical Hydroperiods**

Wetland Type	Hydroperiod			
	Spring Freshet (late February to April 30)	Summer (May - August)	Fall (September - November)	Winter (December - Early February)
<b>Willow Thicket Mineral Swamp (SWT2-2)</b>	5-30 cm water depth with peaks up to 60 cm depth that dry down to 15 cm (or less) within 6 days	5-15 cm water depth with storm event peaks up to 60 cm depth that dry back down to 15 cm (or less) within 6 days. Can also go dry (0) for part of summer.	Same as spring	Frozen condition
<b>Cattail Shallow Marsh (MAS2-1)</b>	30-55 cm water depth with peak events drying back down to 45 cm (or less) within 1.5 months	Can have brief dry-down (several weeks to month) otherwise same as spring	Same as spring	Frozen condition
<b>Mineral Meadow Marsh (MAM2)</b>	0-30 cm water depth	Can go dry much or summer or periodically rewet (0-30 cm)	5-30 cm	Frozen condition



A water availability analysis was carried out for each of the three Wetland Compensation Areas (1, 2, 3) and the Drainage Realignment Wetland Enhancement to assess whether the vegetation communities will be at risk due to drought conditions (**Table 4**), and whether they can be supported by precipitation alone. The present-day typical quantities of precipitation in the region will be compared to the expected levels of evapotranspiration. Integrating climate change considerations into water balance modeling involves incorporating projected changes in climate variables, such as the temperature, precipitation, evapotranspiration, and runoff, into existing water balance models. To account for climate change, the present-day results mentioned previously were compared against data from a 2041-2070s projection. The projected data, retrieved from a database developed by Environment and Climate Change Canada (ECCC), the Computer Research Institute of Montreal (CRIM), Ouranos, the Pacific Climate Impacts Consortium (PCIC), The Prairie Climate Centre (PCC), and HabitatSeven (ClimateData.ca, 2024). An ensemble of 16 climate models were used in the analysis to run plausible futures under a “business as usual” Representative Concentration Pathway (RCP) 8.5 emission scenario. An ensemble, or multi-model approach uses multiple models together to produce a full range of possible climate scenarios.

The water balance accounting methodology, developed by Thornthwaite and Mather (1957), equates the precipitation (P) over a given area to the summation of the change in ground water storage (S), evapotranspiration/evaporation (ET), surface water runoff (R) and infiltration (I) using the following equation:

- Precipitation (P): For the purposes of approximating the annual precipitation at this site, the monthly rainfall between 1981 and 2010 was used based on Environment Canada historical weather data from the “Albion Field Station” weather station (Climate ID 6150103, Latitude 43.92 N, Longitude -79.87 W, Elevation 221.0 metres), located about 11 km east of the site.
- Storage (S): Although there are groundwater storage gains and losses on a short-term basis, the net change in groundwater storage on a long-term basis is assumed to be zero due to the subsurface conditions (silty clay till).
- Evapotranspiration/Evaporation (PET): The evapotranspiration and evaporation components vary based on the characteristics of the land surface cover (i.e., type of vegetation, soil moisture conditions, perviousness of surfaces, etc.). Potential evaporation refers to total possible evaporation given an average monthly temperature, while the actual evaporation only includes the amount of water available as rainfall or storage.
- Water Surplus (R + I): The difference between the mean precipitation and evapotranspiration is referred to as the water surplus. The water surplus is divided into two parts: as surface or overland runoff (R) and the infiltration into the surficial soil (I).

The analytical approach to calculate the water balance involves monthly soil-moisture balance calculations to determine the pre-development infiltration volumes. The following assumptions were used as part of the soil-moisture balance calculations:

- A soil moisture balance approach assumes that soils do not release water as potential recharge while a soil moisture deficit exists.





- During wetter periods, any excess of precipitation over evapotranspiration first goes to restore soil moisture. Considering the nature of the near surface soils (silty clay till) and a combination of wooded and wetland vegetation, a soil moisture storage capacity of 200 mm was used for the wetlands.
- Once the soil moisture deficit is overcome, any further excess water can then pass through the soil as infiltration and either become standing water, interflow (indirect runoff) or recharge (deep infiltration).

Monthly potential evapotranspiration calculations accounting for latitude, climate and the actual evapotranspiration and water surplus components of the water balance based on the monthly precipitation and soil moisture conditions were calculated. Due to the clay to silt-textured till surficial geology in the study area, it is assumed that the majority of a given month's surplus will remain above the surface as standing water within the wetlands.

The area of the proposed riparian wetlands are 1.05 ha and tableland wetlands are 0.35 ha (**Table 2**). For the purposes of the water balance calculation, Wetland Compensation 1 was combined with the drainage feature realignment enhancement wetlands. As all wetlands consist entirely of vegetated area, no impermeable surfaces were accounted for.

The floodplain wetland and tableland wetland designs can be found on **Sheet G-05 (Appendix B)**.

There is limited surface water exchange between the Wetland Compensation Area 2 and the realigned channel (<1 mm change during a 12-hour, 2-year design storm). The same applies for Wetland Compensation Area 3, which will only receive external flows during storms, from the rooftop drainage system. As such, a worst-case scenario was adopted for the water balance, where it was calculated that water levels in both Wetland Compensation Areas 2 and 3 would be sustainable under precipitation exclusively. The recommended quantities shall be perceived as maximum values, as it is normal for wetlands to experience less than maximum water levels in a typical year.

**Table 5** and **Table 6**, below, show monthly soil moisture levels in a typical year, for present-day conditions and the 2041-2070s conditions respectively.

**Table 5 - Monthly Water Balance Results - Present Day Soil Moisture Conditions**

	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
Av. Temp (°C)	-7.0	-5.9	-1.4	6.1	12.4	17.3	19.9	19.1	14.3	8.1	2.1	-3.9
Precip. (mm)	60.4	50.2	50.3	67.0	76.1	75.5	81.8	77.4	75.0	68.3	81.7	57.7
PET (mm)	0.0	0.0	0.0	32.6	77.3	110.5	130.0	114.9	73.5	36.5	7.5	0.0
P – PET (mm)	60.4	50.2	50.3	34.4	-1.2	-35.0	-48.2	-37.5	1.5	31.8	74.2	57.7
Δ Storage (mm)	0.0	0.0	0.0	0.0	-1.2	-35.0	-48.2	-37.5	1.5	31.8	74.2	0.0
Storage Lev. (mm)	200.0	200.0	200.0	200.0	198.8	163.9	115.6	78.1	79.6	111.4	185.5	200.0



**Table 6 - Water Balance Results (2041 – 2070 Soil Moisture Projected Conditions)**

	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
Av. Temp (°C)	-2.8	-2.0	2.2	9.1	15.7	21.0	24.2	23.4	19.0	12.5	6.2	0.6
Precip. (mm)	61.8	57.4	64.4	79.7	72.8	69.1	59.3	68.7	66.8	62.0	77.4	72.5
PET (mm)	0.0	0.0	5.5	38.1	87.2	128.0	156.1	138.2	91.2	47.5	16.2	0.8
P – PET (mm)	61.8	57.4	58.9	41.6	-14.3	-59.0	-96.8	-69.6	-24.4	14.4	61.2	71.8
Δ Storage (mm)	0.0	0.0	0.0	0.0	-14.3	-59.0	-96.8	-69.6	-24.4	14.4	61.2	71.8
Storage Lev. (mm)	200.0	200.0	200.0	200.0	185.7	126.7	29.9	0.0	0.0	14.4	75.6	147.3

Once the general water balance was calculated for the Study Area, the normalized parameters were applied to the individual Compensation Wetland Areas to establish volumetric requirements. **Table 7** and **Table 8** below, show the annual precipitation, evapotranspiration, and greatest monthly deficit for each wetland, volumetrically. The greatest monthly deficit is defined as the volume of water required to overcome the greatest monthly discrepancy between precipitation and evapotranspiration.

**Table 7 - Water Balance Summary - Present Day Precipitation, Evapotranspiration, and Deficits**

Wetland Compensation Area	Annual Precipitation (m <sup>3</sup> )	Annual Evapotranspiration (m <sup>3</sup> )	Greatest Monthly Deficit (m <sup>3</sup> )
Drainage Realignment Enhancement & Compensation Area 1	5254	3731	308
Compensation Area 2	3522	2501	207
Compensation Area 3	2874	2041	169

**Table 8 - Water Balance Summary (2041 - 2070 Project Precipitation, Evapotranspiration and Deficits)**

Wetland Compensation Area	Annual Precipitation (m <sup>3</sup> )	Annual Evapotranspiration (m <sup>3</sup> )	Greatest Monthly Deficit (m <sup>3</sup> )
Drainage Realignment Enhancement & Compensation Area 1	5222	4538	620
Compensation Area 2	3501	3042	415
Compensation Area 3	2856	2482	339



The Thornthwaite Mather water balance results from the present-day climate scenario suggest that groundwater and wetland storage are maintained at a reasonable level. As seen in Table 5, in a typical year, the storage in the system never fully depletes, reaching a minimum soil moisture capacity of approximately 78 mm in the month of August. The minimum soil moisture is reached one month after the greatest monthly deficit occurs, in July.

Contrarily, when using a data representing the '2050s', the storage in the system dries up completely in August, with recovery beginning in October. The increased temperature results in greater evapotranspiration and coupled with the decrease in summer-time precipitation, conditions become favourable for drought. Since drought conditions prove unfavourable for wetland flora and fauna, some recommendations are made for future planning submissions to improve climate resilience for each Compensation Wetland Area, and include:

- All Compensation Wetlands - A detailed investigation into the groundwater conditions in the area, and whether groundwater recharge into the wetland could act as a water source;
- Wetland Compensation Area 1 and Drainage Realignment Enhancement Wetlands – This area is associated with the lowest drought-risk amongst the three compensation areas, due to its proximity to the realigned channel. Should drought conditions persist such that the realigned channel does not spill over into these wetlands in a frequent enough manner, modifications to the bank threshold elevations near the individual wetland can be made to promote more frequent inundation;
- Wetland Compensation Area 2 – Should drought conditions become an issue in Wetland Compensation Area 2, lowering the threshold elevation of the ingress channel would result in greater and more frequent flow from the realigned drainage feature into the floodplain wetland. Additionally completely removing the bypass channel around the Wetland Compensation Area 2 would result in a 100% diversion of flow from the watercourse into the wetland; and
- Increasing the volume (i.e., monthly, annual) of roof water that hydrologically supports Wetland Compensation Area 3 would help mitigate adverse effects of drought conditions for this analysis, a worst-scenario was adopted, where no inputs outside of precipitation were assumed to supplement the water in the three Compensation Wetland Areas.

These adaptive measures can be implemented as necessary through the Long-Term Monitoring and Adaptive Management process for the Study Area (**Table 3, Appendix C**).

#### 2.4.3.2 Terrestrial Crayfish SWH Compensation Area

The small wetland (Wetland C1) next to the FOD8-3 provides Terrestrial Crayfish SWH and is proposed for partial removal, (0.30 ha) and compensation to accommodate the Prologis Site Plan. Terrestrial Crayfish are closely associated with clay substrates and wetlands where groundwater is close to the surface. There are two recommended options for habitat compensation to support terrestrial crayfish repopulation:

1. Retain a portion of the original wetland habitat which allows for natural recolonization by the terrestrial crayfish; and
2. Retain headwater contributions and create new habitat downstream from the original habitat to allow for contributions from upstream habitat.



A portion of Wetland C1 will be retained, while the rest will be compensated for through Wetland Compensation Area 2. With a headwater drainage feature connection young crayfish will flush down to available wetland habitat where a breeding population can be established between 2-3 years (Savanta, 2019). Based on the Compensation Wetland 2 design discussed in **Section 2.4.3**, this compensation habitat should provide a suitable area for repopulation of terrestrial crayfish. To support appropriate habitat compensation to offset the encroachment, the newly created wetland associated with the drainage feature realignment will connect to the retained wetland area to ensure that spring freshet conditions can support repopulation of the new wetland feature.

To accommodate the life cycle of terrestrial crayfish, habitat removals should occur in summer months when terrestrial crayfish burrow deepest into the substrate to limit disruption; no removals should occur during spring when terrestrial crayfish are closest to the surface.

Vegetation removal within terrestrial crayfish habitat to be removed will require bird nest sweep surveys when within Migratory Birds Convention Act (1994) window. All tree removals within terrestrial crayfish habitat to be completed outside of the active windows for breeding birds and bats (March 15 to November 30), or bat exit surveys are required.

The retained portions of the SWH and the compensation area will be further protected by a 10 m vegetated buffer to provide important foraging habitat and protection to the wetland and SWH from sedimentation and surface water runoff.

#### 2.4.3.3 Redside Dace Contributing Habitat Compensation Area

Some HDFs providing contributing habitat for Redside Dace (i.e., portions of HDF-8 and HDFs 4a, 10a, 11a, 12a, 13a, and 15a) are proposed for removal and replication of functions. These features are degraded due to ongoing agricultural practices, resulting in siltation from being ploughed through, and pollution from fertilizers.

Replication and enhancement of functions (baseflow and coarse sediment supply) is anticipated to be achieved through SWM Ponds 1 and 3, and Wetland Compensation Area 3. Ponds 1 and 3 will have extended detention (25 mm event over 48 hours) and are designed to deliver enhanced protection by maintaining a permanent pool, achieving an 80% removal of total suspended solids (TSS). The permanent pools will be 3 m deep for thermal mitigation.

Wetland Compensation Area 3 has been designed to replicate and enhance Redside Dace contributing habitat functions by improving water quality and lowering water temperatures. Flow contributions will be conveyed from rooftops to support the hydrology of the wetland; this is anticipated to support the water volume input as outlined in the water balance assessment (Section 2.4.3.1). Water polishing is expected as flows are conveyed through the Wetland Compensation Area 3. Riparian plantings within the 10 m VPZ for this wetland will also contribute to thermal mitigation for this feature.

Both SWM Ponds 1 and 3 and Wetland Compensation Area 3 will outlet to alluvium deposits to deliver coarse sediment supply to downstream habitat. Compared to the existing impairment due to active agriculture described above, the proposed mitigation is expected to be a considerable improvement.



As the lands within the Humber Station Employment Lands move through subsequent planning applications, adherence to the MNRF's Guidance for Development Activities in Redside Dace Protected Habitat (2016) and the Thermal Mitigation Checklist for Stormwater Management Ponds Discharging into Redside Dace Habitat (2014) is recommended to support the final design of compensation wetlands, stormwater ponds, and low impact development solutions as contemplated in the Phase 2 CEISMP.

#### **2.4.4 Compensation Woodland**

A portion of Fresh-Moist Lowland deciduous forest (FOD8-3) within Woodland 2 is proposed for removal and compensation to accommodate shifting the proposed drainage feature alignment to the west to provide the needed area for an industrial building footprint.

As outlined in the Phase 2 CEISMP, this woodland feature is considered a Core Woodland Area in the Town of Caledon Official Plan (2018). To support the removal of 0.06 ha of FOD8-3 (the remainder of the 0.34 ha of removals is CUT and CUM1), the Humber Station Employment Area Secondary Plan policies (Section 7.16.7.3) have been revised to permit minor encroachment and compensation as outlined in an approved CEISMP and EMP. This is based on the principal that the total native woodland removal is small (0.06 ha of the total 0.34 ha removal), and that final preliminary NHS will provide for an improved system with enhanced native woodlands, invasive species management, and improved NHS connectivity.

The woodland compensation is targeting a lowland deciduous forest community, with a treed canopy cover of 75% or greater once established on the landscape. A Fresh-moist Oak – Maple – Hickory Deciduous Forest (FOD9) is targeted for the compensation woodland. The FOD9 communities are generally a mix of upland and lowland/wetland species suitable for a riparian area. These communities are typically characterized by loam and clay soil textures, which are found within the Study Area, as well as species that are typically observed throughout the Study Area, such as Red Oak (*Quercus rubra*), White Oak (*Quercus alba*), Bur Oak (*Quercus macrocarpa*), Sugar Maple (*Acer saccharum*), Red Maple (*Acer rubrum*), Shagbark Hickory (*Carya ovata*) and Bitternut Hickory (*Carya cordiformis*) with the inclusion of sedge and fern species.

The Compensation Woodland is planned adjacent to the extended floodplain surrounding Compensation Wetland Area 2. This is appropriately located as the partially removed woodland was adjacent to HDF-3 and its associated wetlands and will ensure that connectivity between these features is maintained in the NHS.

#### **2.4.5 Amphibian Habitat Creation**

The proposed development requires the removal of wetlands and woodlands; some of which provide suitable habitat conditions for four amphibian species, as noted below. Amphibian habitat creation, for those removals/realignment, is targeted to be created with woodland, wetland and proposed drainage channel realignment design.



Pre-development amphibian habitat proposed for realignment and compensation:

### **American Toad**

- Breeding habitat: Marshes;
- Summer habitat: Woodland habitat; and
- Overwintering habitat: Hibernates terrestrially, burrows into soil below frost line.

### **Green Frog**

- Breeding habitat: Stream banks;
- Summer habitat: Moist woodlands near water and riparian areas; and
- Overwintering habitat: Adults and tadpoles overwinter aquatically in the breeding pond or adults may move to another pond.

### **Grey Tree Frog**

- Breeding Habitat: Marshes;
- Summer Habitat: Upland areas within forested or thicket habitats; and
- Overwintering Habitat: Hibernates terrestrially, within logs, tree roots or under leaf litter.

### **Northern Leopard Frog**

- Breeding Habitat: Ephemeral wetlands, and stream banks; and
- Summer Habitat: Generalist species that are observed in a variety of habitat types, with a preference for more open communities.

Compensation wetlands to support amphibian habitat are generally designed with shallow slopes (4:1 to 8:1) facing suitable habitats to enable amphibians to move between the replicated wetlands and surrounding habitat (i.e., riparian and upland summer habitats). Shallow slopes provide a wide littoral zone to support emergent, meadow marsh and shrub vegetation. This vegetation provides egg attachment sites (e.g., emergent vegetation, branches), foraging habitat for insects (food source), shelter from predators, and overwintering habitat for some species. Steeper slope grading can also be beneficial where the wetland polygon fronts the proposed development, to discourage wildlife movement towards development/roadways. Deciduous trees and shrubs are recommended to provide partial shade and leaf litter that will regulate wetland temperature and provide shelter sites and potential terrestrial overwintering habitat. Woody roots that interact with the littoral wetland zone can also serve as refugia and egg attachment sites.



## 2.5 Fluvial and Ecological Considerations for Stormwater Management Pond Outfall Location and Design

It is recommended that the proposed stormwater management pond outlets be placed entirely outside of natural heritage features (i.e., above staked top of bank, outside of woodland and wetland setbacks) with their outfalls placed and designed in collaboration with a fluvial geomorphologist to avoid erosion and sedimentation. Energy dissipation measures, such as a pocket wetland is recommended at the outlet, to reduce erosive forces downstream of the outlet. The pocket wetland would include a stone core, comprised of hydraulically sized substrate, designed to withstand the outlet's flow range. A layer of hydric soil is placed above the stone core and seeded with native vegetation. The pocket wetland would be intended to provide additional retention functions and promote infiltration within the feature. A level spreader at the wetland's outlet would allow dispersion of overland flow once the retention capacity is reached.

## 2.6 Restoration and Enhancement Plan Summary

The proposed preliminary NHS is planned to contain:

- One north-south corridor:
  - Through the retained Clarkway Drive Tributary valley.
- One east-west corridor:
  - Connecting Proposed Drainage Feature Realignment to the Clarkway Tributary valley through Wetland Compensation Area 2 and Woodland Compensation Area.
- Additional NHS connectivity:
  - North-south through the proposed HDF-3 Drainage Feature Realignment; and
  - West-east through the Clarkway Drive Tributary to Wetland Compensation Area 3.
- 10 m wide native vegetation planted buffer between woodlands (significant and non-significant) and development;
- 10 m wide native vegetation planted buffer between local wetlands and wetland compensation areas and development;
- 30 m wide native vegetation planted buffer between Significant Wetlands and development;
- 15 m wide native vegetation planted buffer between warm water fish habitat and development;
- 10 m setbacks from the staked Top of Bank, Regional Floodline, and 100 Year Floodline;
- 0.35 ha of woodland compensation;
- 1.40 ha of wetland compensation (riparian online and offline wetlands, tableland wetland);
- 1,438 m of realigned drainage channel length (representing a net gain of 351 m);
- Amphibian habitat creation (compensation wetland, woodland, drainage feature realignment);



- Redside Dace contributing habitat compensation (Wetland Compensation Area 3) with a 10 m wide native vegetation planted buffer (for partial removal of HDF-8 and 4a, 10a, 11a, 12a, 13a, and 15a); and
- Terrestrial Crayfish habitat with a 10 m wide native vegetation planted buffer (retained portions Wetland C1 and Wetland Compensation Area 2).

In addition, the following restoration actions are proposed to support a more robust preliminary NHS:

- Targeted Invasive Species Mapping and Environmental Management Plan for Common Buckthorn, Phragmites and White Poplar;
- Relocation of one Barn Swallow replacement structure (50 m) to accommodate the proposed drainage feature realignment. The replacement structure will remain inside the NHS;
- Where feasible, salvage and transplant of rare specie(s) will be relocated from removed habitats into compensation habitats; and
- Stormwater Management Pond outfalls designed with stone size appropriate for the hydraulic gradient and suitable for native seeding.





## 3. NHS Implementation Plan

---

The implementation of the Humber Station Employment Area Natural Heritage System is informed by planning, engineering and ecological constraints and opportunities during construction. This section includes the land ownership plan (including non-participants), provides a sequencing (phasing) for servicing and buildout, includes a Natural Heritage System Implementation (Phasing) Plan in consideration of agency permitting and wildlife windows and indicates LOG responsibilities for implementation.

### 3.1 Implementation Considerations

The successful delivery of various components of the NHS requires an implementation plan that considers the following items:

- maintaining the environmental integrity of the existing NHS;
- sequencing of site works to maximize the ability to deliver the proposed NHS in a timely manner and integrating NHS delivery with development phasing plans;
- following agency required wildlife construction windows;
- cold-climate construction season as it relates to the “growing season”;
- erosion and sediment prevention and control;
- co-operation amongst the developers, consultants and Approval Agencies; and
- creativity and flexibility in solving implementation challenges.

A conceptual Natural Heritage System Implementation (Phasing) Plan is provided in **Table 9 (Appendix C)**; however, each individual subdivision will require detailed implementation plans as part of subsequent planning applications.

### 3.2 Phased Buildout and Site Accessibility

The Humber Station Employment Lands Area will be developed in phases. The initial phase of build out within the Study Area will be to support the Site Plan Application for the Prologis Phase 1A development (the George Bolton Parkway Extension). This initial phase will include interim servicing of this Phase 1A building, road design, and construction of the channel realignment and wetland enhancement, wetland compensation (1 and 2), woodland compensation and the removal of a portion of HDF-8.

The majority of the proposed development is within the Humber Station Landowner Group land holdings, see Landownership Plan (**Figure 4, Appendix A**), however there will be restricted access to direct flows to the parcel where Wetland Compensation Area 3 and SWM Pond 3 will be constructed due to the non-participating property that separates parcels owned by Ballantry Homes. It is expected that this will be facilitated when this non-participating owner becomes a participant.

The remaining servicing, road structure and construction, will commence at a later phase once access is resolved.



### **3.3 Permitting Requirements to Agencies or other Parties**

This section provides guidance for various regulatory permitting requirements necessary for the implementation of the development in the Humber Station Employment Area and in particular, the NHS, site grading and servicing.

#### ***Department of Fisheries and Oceans***

The Fisheries Act permits may be required for any activities that may result in the death of fish, or the harmful alteration, disruption or destruction of fish habitat as prohibited under the Fisheries Act. This may extend to any fish salvage or rescue that is required to support the ecological compensation efforts; a Scientific Collectors Permit is required to carry out this work. Should removal of no management, mitigation or conservation HDFs' or culvert replacement occur when standing water is present (seasonal fish habitat) an MNRF permitted fish rescue will be required.

#### ***Toronto and Region Conservation Authority***

As per the Conservation Authorities Act, permits will be required for development regulated areas (as per O.Reg 41/24: Prohibited Activities, Exemptions and Permits). This permit type will be required for the alteration and compensation of all regulated wetlands and the drainage feature realignment (HDF-3) within the Study Area.

#### ***Ministry of Environment***

*Ontario Water Resources Act* Certificate of Approval for SWM – All infrastructure (storm sewers, sanitary sewers, and watermains) requires a Certificate of Approval from the Ministry of the Environment (MOE). SWM facilities discharging into watercourses also require MOE review and certification; this typically involves submission of detailed facility design reports demonstrating conformance to approved SWM targets.

*Ontario Water Resources Act* Permit-to-Take-Water – Depending on the quantity of dewatering required during construction, a temporary Permit to Take Water (PTTW) may be required from the MOE (for quantities that exceed 50,000 L/day). The application for a PTTW will require supporting hydrogeological information, an assessment of potential impacts related to the dewatering, proposed monitoring and mitigation plans as well as details of the proposed location of discharged flows.

#### ***Ministry of Environment, Conservation and Parks***

*Endangered Species Act* (2007) - Authorization under clause 17(2)(c) of the *Endangered Species Act* for an Overall Benefit Permit may be required for activities that involve alterations to contributing habitat for Redside Dace. An Information Gathering Form will need to be submitted to the MECP as part of the Draft Plan stage to demonstrate how direct and indirect impacts to Endangered and Threatened species will be mitigated. Permits may also be required for potential impacts/alterations to other species at risk within the Study Area should any alterations be proposed in subsequent planning applications.



## **Town of Caledon**

A Woodland Permit (for tree removals under By-law 2000-100 'Woodland Conservation'), and non-woodland trees proposed for removal and their required compensation should be evaluated through an appropriately scoped Arborist Report and Tree Preservation Plan, in alignment with the Town of Caledon's Terms of Reference (Caledon, 2020).

A Site Alteration Permit, Pre-Servicing Agreement, Topsoil Stripping Permit and Construction Access Permit must also be obtained from the Town.

The various departments of the Town must also approve the trail system, park design, landscaping, general site grading and servicing, including underground (storm, sanitary, and water), above-ground design, SWM facility design and maintenance plans. This approval process will be required as part of subsequent planning applications for the Study Area.

### **3.4 Sequencing of servicing, NHS construction and build-out**

The Humber Station Employment Area Natural Heritage System Implementation (Phasing) Plan (**Table 9, Appendix C**) provides the sequence of natural feature removal and NHS construction (compensation features, NHS buffers), providing constraints windows for each action.

To support sequencing for servicing and construction, a Wildlife Construction Window Table was prepared (**Table 10, Appendix C**) which summarizes the constraints and timing for construction to protect fish, bat, bird, amphibian and reptile habitat.

Additional discussion on construction and conveyance and dewatering is provided in the sections below.

#### **3.4.1 Construction and Conveyance**

The following are best practices and guidelines that should be followed as part of the construction and conveyance of the Study Area:

- The isolation of in-stream work areas for the proposed drainage feature re-alignment is preferred to facilitate construction "in-the-dry" and thereby mitigate against the risk of downstream sediment transport while construction of the realigned drainage feature takes place;
- The current site plan does not propose any municipal services under the retained or proposed NHS. Should this change in future individual planning submission applications the construction of municipal services and road crossings of the NHS should be completed prior to the construction of any proposed NHS features (i.e., drainage feature, wetland);
- Soil investigations, along the proposed drainage feature realignment, Compensation Wetlands 1, 2 and 3 and the Woodland Compensation Area is required to assess the potential for encountering layers of high hydraulic conductivity sediments;



- Where the site is being cut, topsoil and subsoil will be stockpiled, and topsoil will be tested for suitable plant growth prior to re-use on site as per TRCAs Health Soil Guidelines (2012);
- An assessment of the dewatering requirements for construction will be made based on the detailed construction plans (See **Section 3.4.2** for more information on dewatering recommendations). Management and mitigation plans will be developed to address groundwater control as well as the potential for long-term water table lowering. A Temporary Permit to Take Water (PTTW) may be required from the MECP depending on the anticipated quantity of dewatering required during construction;
- Rigorous erosion and sediment control measures must be designed, implemented and maintained throughout the construction period. At detailed design, an Erosion and Sediment Control Plan will be prepared and designed in conformance with the Town and TRCA guidelines. Erosion and sediment control will be implemented for all construction activities including topsoil stripping, earthworks, foundation excavation and stockpiling of materials and will remain in place and functional until bare surfaces are stabilized. Reference should be made to the *Erosion and Sediment Control Guide for Urban Construction (TRCA, 2019)* when preparing Erosion and Sediment Control Plans;
- The following erosion and sediment control measures should be considered for use during construction:
  - Natural features will be staked, and temporary fencing provided to keep machinery out of sensitive areas;
  - Sediment control fence and snow fence will be placed prior to earthwork;
  - Logistics/construction plan will be implemented to limit the size of disturbed areas, minimizing the non-essential clearing and grading areas;
  - Temporary sediment ponds will be utilized;
  - Rock check-dams and cut-off swales will be provided, where required, in order to control, slow down and direct runoff to sediment basins;
  - Sediment traps will be provided; and
  - Gravel mud mats will be installed at construction vehicle access points to minimize off-site tracking of sediments.
- All temporary erosion and sediment control measures will be routinely inspected/monitored and repaired during construction. Temporary controls will not be removed until the areas they serve are restored and stable;
- The “multiple barrier approach” will be applied to all construction stages to ensure erosion is prevented rather than reduced. Recommended measures are to be installed prior to the initiation of the earthworks and grading;
- All temporary erosion and sediment control measures will be routinely inspected and repaired during construction. Temporary controls will not be removed until the areas they serve are restored and stable. A third-party inspector will be involved to assess the temporary sediment and erosion control measures;



- Adequate riparian storage must be maintained, to the extent feasible, during construction periods:
  - Timing restrictions are typically imposed on in-stream work to avoid periods when fish are spawning. Eggs and embryos may be present at these stages and are particularly sensitive to sediment. In Ontario, most fish spawn in the spring, but some species spawn during the mid-to-late fall period. HDFs' proposed for removal that provide seasonal warmwater fish habitat, to be removed (following permitted fish rescue) July 16 through March 14. Should an HDF be dry outside of warmwater fish window, HDF removal can occur outside of this window and without fish rescue. Based upon the presence of Redside Dace contributing habitat within HDFs', in-water work is to adhere to the Redside Dace timing window, which is July 1<sup>st</sup> to September 15<sup>th</sup>. (These timing windows are guidelines, and some flexibility exists in these dates; however, approval from the TRCA and MECP is required for deviations from these timelines and stabilization strategies). Should HDF-3 removal occur during dry period, MECP may authorize removal outside of Redside Dace in-water works window;
- Practical measures for the maintenance of seasonal water levels in retained wetlands and watercourses during construction, as well as monitoring requirements, must be identified and implemented, where feasible;
- The construction and conveyance of the projects to public ownership will be implemented through agreements between the landowners and the Town. These agreements will address extent of works, construction phasing, securities requirements, conveyance mechanisms, etc.; and
  - Generally appropriate timings for the above measures are included in **Table 9 (Appendix C)**.

### **3.4.2 Dewatering Requirements**

Dewatering will be required for construction along the proposed drainage feature realignment, construction of the stormwater management ponds, Wetland Compensation Area 3 in the southeast portion of the Study Area, the installation of the LID facility near HDF-3 east of Humber Station Road, and for the installation of the sanitary sewers, storm sewers, and watermains along the proposed George Bolton Parkway and Street A2 where sewer trench grades and excavations encounter groundwater.

Site-specific dewatering requirements will be assessed at detailed design. However, as noted in the Phase 2 CEISMP report, due to the proposed depths of the sanitary sewers, particularly along George Bolton Parkway and the north end of Street A2, the lower confined aquifer may need to be depressurized prior to start of construction activities. The dewatering and depressurization assessment included in the Phase 2 CEISMP report and summarized below should be considered preliminary. Additional data will be required along the proposed alignments to adequately assess potential dewatering requirements for permitting purposes, as well the associated monitoring and mitigation measures.



Based on the information available to date however, the approximate dewatering/depressurization rate that may be required for George Bolton Parkway may be more than 1,900 m<sup>3</sup>/day (1,900,000 L/day) and would require positive dewatering techniques (e.g., wellpoints, eductor wells and/or deep wells).

Positive dewatering involves pre-drainage, which includes dewatering and depressurization, and lowering the water level to a safe distance below the target excavation depth before the excavation occurs. The approximate corresponding zone of influence (ZOI) associated with this dewatering is estimated to be almost 1,900 m and would intercept the Clarkway Drive Tributary, which has been mapped as Redside Dace contributing habitat. The ZOI may also intersect tributaries of the West Humber River west of the Study Area and private domestic water supply wells within the ZOI. **Figure 5 (Appendix A)** illustrates the approximate interpreted ZOI associated with depressurization using conservative assumptions.

For positive dewatering, three dewatering discharge options were identified:

- Discharge to vegetated areas as dispersed flow (using perforated pipes, sprinkler systems and other dispersion technologies) or as sheet flow with need to demonstrate that this will not adversely impact natural feature hydrology and/or result in vegetation/sediment loss;
- Discharge to temporary sediment pond or the SWM facilities; and
- Discharge to watercourse following pre-treatment.

Conversely, for areas of shallow services or excavations such as the south end of Street A2, or the proposed SWM Pond 3 and Stormwater Tank (located at the west side of the George Bolton Parkway) (**Figure 3, Appendix A**), the estimated preliminary dewatering rates are relatively low (<5 m<sup>3</sup>/day for any respective area) and the corresponding ZOI is also limited (~ <5 m). For these areas, passive dewatering should be sufficient. Passive methods of dewatering include drainage via gravity and manual pumping via sump pumps or similar. Passive methods typically produce lower flows than positive methods of dewatering and have only a localized influence on the water table. Passive methods are generally used in low permeability systems, shallow perched systems or following precipitation events.

Passive methods of dewatering are used by the contractor on an as-needed basis. In this regard, some amount of passive dewatering is anticipated but would not be known until construction is underway. Any dewatering is discharged using a properly constructed sump pump that consists of a perforated vertical collector pipe wrapped in geotextile fabric. The pump is positioned within the excavation and backfilled with clean stone. The resulting clean discharge is typically directed to the nearest sediment control measure on site, such as sedimentation ponds or drainage swales.

For construction dewatering, water takings of more than 50,000 L/day but less than 400,000 L/day may be registered on the Environmental Activity and Sector Registry (EASR), while water takings of more than 400,000 L/day require a PTTW issued by the MECP. Should the construction contractor need to pump at rates > 50,000 L/day and up to 400,000 L/day the EASR for construction dewatering will be required from the MECP. The EASR will need to be obtained in accordance with the provincial regulations prior to dewatering activities.



It is a requirement during any construction dewatering program that appropriate monitoring of the local groundwater levels and surface water features (wetlands and watercourses) adjacent to the dewatering area be conducted. Should the monitoring indicate a radius of influence that could adversely affect the groundwater levels in adjacent natural features or interfere with groundwater supplies to local water wells, mitigation measures must be designed to compensate for the effects.

Once the estimated dewatering rates are confirmed, the long-term monitoring plan (LTMP) and comprehensive adaptive management plan (CAMP) presented in the Phase 3 CEISMP will need to be reviewed and confirmed. A key objective of the LTMP is to distinguish potential groundwater-related impacts from natural trends at an early stage. This will provide an ability to focus monitoring to help determine the how/why/frequency of potential impacts and will assess cause-effect relationships between the environment and land use change.

### **3.4.3 Water Table Lowering**

Urban development has the potential to lower the groundwater table as a result of reduced infiltration. In addition, the construction of buried services below the water table has the potential to capture and redirect groundwater flow through more permeable fill materials placed in the base of excavated trenches and may result in an overall lowering of the water table. However, services below the water table will be constructed to prevent redirection of flow. This will involve the use of anti-seepage collars or clay plugs surrounding the pipes to provide barriers to flow to prevent drainage of groundwater flow along granular bedding and erosion of the backfill materials.

Seasonally high-water table conditions have been documented in all retained wetlands across the Study Area, see the Phase 2 CEISMP Wetland Characterization Tables for details. As such, it is important to maintain the high-water table conditions in the wetland areas during, and post construction. Prior to channel construction, detailed soil investigations are recommended along the proposed alignment, focusing on the areas adjacent to the wetlands. This may involve the excavation of test pits or drilling of boreholes to assess the soil and groundwater conditions.

Where shallow coarse-grained sediment layers are encountered during the soil investigations, the potential groundwater yield from these zones will be assessed through field testing. This may involve borehole hydraulic conductivity testing and/or short-term pumping tests to determine the need for active dewatering for channel construction. It may also involve the assessment of the potential for longer-term impacts on the local water table conditions relative to any permanent dewatering that would occur if a permeable layer continued to drain into the channel (i.e., calculation of the potential radius of influence for water table lowering). In such circumstances, mitigation strategies for the control of groundwater during construction and, if warranted, mitigation to prevent lowering of the water table over the long term, will be required. During construction, collection and discharge of groundwater seepage back to the wetland feature may be considered should it be demonstrated that this activity maintains monthly pre-development hydrological conditions. Mitigation measures for long-term impacts may involve the installation of cutoff walls or barriers to prevent groundwater from continuing to drain from the sand layer into the channel. Contingency plans for construction will also be required should a zone of higher hydraulic conductivity be encountered unexpectedly during the excavations.



### **3.4.4 Private Well Water Supplies and Well Decommissioning**

The proposed development will be municipally serviced and the existing groundwater supply wells within the Study Area will be decommissioned as the development proceeds. In the interim, it is important to ensure that construction does not adversely affect local groundwater supplies while the private water supply wells are still in use.

The Region requires monitoring of private wells throughout the construction period. Typically monitoring of private wells within 500 m of proposed construction works; however, an expanded monitoring program may be required if the zone of influence associated with dewatering and depressurization of the deep services is confirmed to be greater than 500 m. Prior to the commencement of earthworks and servicing construction activities, it will be necessary to contact the local residents, who rely on groundwater supply wells, to document the location and condition of their wells and monitor their well conditions (water quantity and quality) throughout the earthworks period. Additional groundwater monitoring specific requirements are outlined in **Table 11 (Appendix C)**.

Prior to construction, it will be necessary to ensure that all inactive water supply wells, within the development footprint, have been located and properly decommissioned by a licensed water well contractor in accordance with Ontario Regulation 903. In addition, all groundwater monitoring and observation wells installed for the Study Area must be decommissioned in accordance with provincial regulations prior to or during the site development, unless they are maintained throughout the construction period for monitoring purposes.

## **3.5 Responsibilities for Implementation**

The implementation (construction) of the Humber Station Employment Area and the natural heritage system, and the implementation of the monitoring program (baseline, during construction, post-construction) is the responsibility of each individual landowner. The exact timing of these activities will be identified through future planning applications.

## **3.6 Implementation Plan Summary**

Key implementation items have been summarized in **Table 9 (Appendix C)**. This includes action items to facilitate protection of features, feature removals, feature realignment, compensation efforts, restoration measures, culvert installations and stormwater management pond creation, the appropriate months for completion, and key considerations for these action items and their timelines. It is expected that this implementation plan will be reviewed and revised as the lands within the Study Area proceed through subsequent planning applications to better reflect site-specific alterations and construction.





## 4. Long Term Monitoring Plan and Comprehensive Adaptive Management Plan

---

The goal of the Phase 3 CEISMP is to compile a multidisciplinary approach for the restoration and enhancement of the NHS to enhance ecological integrity and function, optimize biodiversity and restore natural features. To support this, a proposed long-term monitoring plan (baseline, during construction, post-construction) and comprehensive adaptive management plan is summarized for each discipline (ecology, hydrology, hydrogeology) in **Table 11 (Appendix C)**. The high-level recommendations for monitoring and adaptive management are intended to ensure that the compensation, restoration, and enhancements proposed through the Humber Station Employment Lands preliminary NHS will properly establish to meet the ecological targets outline in **Section 2.3**.



## 5. Conclusions

---

The work proposed in this Phase 3 CEISMP is designed to compensate for proposed wetland, wildlife habitat, and woodland removal, and provide additional natural feature enhancement design through the headwater drainage feature realignment, maintain and enhance existing natural heritage features, improve NHS connectivity, manage invasive species, and increase plant species and vegetation community diversity.

The Phase 3 CEISMP includes the following key components to support the long-term implementation of the NHS within the Humber Station Employment Lands:

- Design of three compensation wetlands that will support several wetland vegetation types;
- Design of a drainage feature realignment to support enhanced aquatic habitat and to facilitate the compensation wetlands and enhancement wetlands;
- Design of compensation woodland that will support native deciduous woodland type;
- Provision of suitable amphibian breeding habitat within created wetlands resulting in an overall increase in amphibian breeding habitat in the Study Area;
- Compensation of appropriate wetland habitat for Terrestrial Crayfish (Species of Special Concern SWH);
- Diverse, native planting prescriptions within the created wetlands, riparian areas around the drainage feature realignment, woodland compensation area, and other restoration areas;
- Replication of Redside Dace contributing habitat functions through the proposed Wetland Compensation Area 3 with improvements to water quality, quantity, and thermal regulation;
- Invasive species management;
- Natural Heritage System implementation considerations;
- Proposed phasing and sequencing of buildout;
- Permitting requirements;
- Responsible parties for implementation; and
- Proposed multi-disciplinary Long-term Monitoring Plan and Comprehensive Adaptive Management Plan.

These actions are intended to support the creation of a robust NHS and meet the NHS ecological targets outlined in Section 2.3.2. The long-term management plan and comprehensive adaptive management plan will support the long-term establishment of the NHS and ensure that there are robust measures in place to ensure the success of ecological form and function in the NHS.



**Prepared By:**

GEI Consultants Canada Ltd.



---

Holly Stemberger  
Environmental Planner  
780-266-2594  
hstemberger@geiconsultants.com

GEI Consultants Canada Ltd.



---

Lukas Mueller  
River Scientist  
519-572-4607  
lmueller@geiconsultants.com

**Prepared and Reviewed By:**

GEI Consultants Canada Ltd.



---

Heather Whitehouse  
Senior Ecologist  
416-568-7284  
hwhitehouse@geiconsultants.com

**Reviewed By:**

GEI Consultants Canada Ltd.



---

George Buckton  
Senior Ecologist  
416-816-2246  
gbuckton@geiconsultants.com

**Reviewed By:**

GEI Consultants Canada Ltd.



---

Ahmed Siddiqui  
Senior Fluvial Geomorphologist  
416-991-3169  
asiddiqui@geiconsultants.com

**Prepared By:**

Arcadis Professional Services (Canada) Inc.



---

Aron Zhao  
Environmental Engineer  
289 815-2975  
aron.zhao@arcadis.com



**Prepared and Reviewed By:**  
Schaeffers Consulting Engineers



---

Koryun Shabbikian  
Partner  
905 738-6100  
kshabbikian@schaeffers.com

**Reviewed By:**  
Arcadis Professional Services (Canada)



---

Steve Davies  
Associate - Manager, Environmental  
Services, Geosciences  
289 815 2975  
steve.davies@arcadis.com



## REFERENCES AND BACKGROUND MATERIALS

---

Canadian Centre for Climate Services. 2023. Climate trends and Projections. Available online: <https://www.canada.ca/en/environment-climate-change/services/climate-change/canadian-centre-climate-services/basics/trends-projections.html>

ClimateData.ca. Climate Data for a Resilient Canada. Accessed August 2024.

*Conservation Authorities Act*, O Reg. 41/24, Prohibited Activities, Exemptions and Permits, R.S.O. 1990, c. C. 27

Gann GD, McDonald T, Walder B, Aronson J, Nelson CR, Jonson J, Hallett JG, Eisenberg C, Guariguata MR, Liu J, Hua F, Echeverria C, Gonzales, EK, Shaw N, Decler K, Dixon KW. 2019. International principles and standards for the practice of ecological restoration. Second edition. *Restoration Ecology* S1-S46

GEI Consultants Canada Ltd. 2024. Phase 1 CEISMP.

Hoffman, D.W., and Richards N.R. 1953. Soil Survey of Peel County. Available online: [https://sis.agr.gc.ca/cansis/publications/surveys/on/on18/on18\\_report.pdf](https://sis.agr.gc.ca/cansis/publications/surveys/on/on18/on18_report.pdf)

Lee, H.T., W.D. Bakowsky, J. Riley, J. Bowles, M. Puddister, P. Uhlig and S. McMurray. 1998. Ecological land classification for Southern Ontario: first approximation and its application. Ontario Ministry of Natural Resources, South Central Region, Science Development and Transfer Branch. Technical Manual ELC-005.

Minister of Justice. 2024. Fisheries Act, 1985. Available online: <https://laws.justice.gc.ca/PDF/F-14.pdf>

Minister of Justice. 2024. Migratory Birds Convention Act, 1994. Available online: <https://laws.justice.gc.ca/PDF/M-7.01.pdf>

Ministry of the Environment, Conservation and Parks (MECP). 2023. Permits to Take Water. Available online: <https://www.ontario.ca/page/permits-take-water#section-0>

Ministry of the Environment. 2024. Ontario Water Resources Act, R.S.O. 1990, c. O. 40. Available online: <https://www.ontario.ca/laws/statute/90o40>

Ministry of the Environment. 2024. R.R.O. 1990, Reg 903: WELLS. Available online: <https://www.ontario.ca/laws/regulation/900903>

Ministry of the Environment, Conservation and Parks (MECP). 2020. Endangered Species Act, 2007. Available online: <https://www.ontario.ca/laws/statute/07e06>

Ministry of Municipal Affairs and Housing (MMAH). 2024. Provincial Policy Statement, 2024. Available online: <https://www.ontario.ca/page/provincial-planning-statement-2024>



Ontario Ministry of Natural Resources (OMNR) 2000. Significant Wildlife Habitat Technical Guide. Fish and Wildlife Branch. Wildlife Section. Science Development and Transfer Branch. Southcentral Sciences Section. 151 pp.

Ministry of Natural Resources (MNR) 2010. Natural Heritage Reference Manual for Natural Heritage Policies of the Provincial Policy Statement, 2005. Second Edition. Toronto Queen's Printer for Ontario. 248 pp.

Ministry of Natural Resources and Forestry (MNRF). 2014. Thermal Mitigation Checklist for Stormwater Management Ponds Discharging into Redside Dace Habitat. Available online here

Ministry of Natural Resources and Forestry (MNRF), 2016. Guidance for Development activities in Redside Dace Protected Habitat. Version 1.2. Peterborough, Ontario, Queen's Printer for Ontario, 2016. 32pp. Available online: <https://www.ontario.ca/page/guidance-development-activities-redside-dace-protected-habitat>

North-South Environmental Inc et. al. 2009. Peel-Caledon Significant Wildlife Habitat Study. Available upon request.

Ontario Invasive Plant Council. Best Management Practices. Available online: <https://www.ontarioinvasiveplants.ca/resources/best-management-practices/>

Ouranos. 2024. Temperatures – Projected Changes. Available online: <https://www.ouranos.ca/en/climate-phenomena/temperatures-projected-changes#:~:text=With%20a%20high%20emissions%20scenario,6%C2%B0C%20for%202080.>

Pacific Climate Impacts Consortium. 2024. Plan2Adapt. Available online: <https://services.pacificclimate.org/plan2adapt/app/>

Pollock, M.M., Beechie, T.J., Imaki, H. 2012. Using reference conditions in ecosystem restoration: an example for riparian conifer forests in the Pacific Northwest. *Ecosphere* 3(11) pp1-23.

Prairie Climate Centre. 2024. Planning for Climate Change. Available online: <https://climateatlas.ca/planning-climate-change>

Region of Peel. 2016. Regional Official Plan Amendment Number 30 – An Amendment to Establish a Bolton Residential Expansion Settlement Area Boundary. Available online: <https://www.peelregion.ca/planning/officialplan/pdfs/ropa-30/revised-ropa-30.pdf>

Region of Peel. 2022. Region of Peel Official Plan. Office Consolidation April 2022. Available online at: <https://www.peelregion.ca/officialplan/download/>

Rowe, J.S. 1972. Forest regions of Canada. Canadian Forest Services. Ottawa.



Savanta Inc and Dr. Hamr. 2019. Terrestrial Crayfish. Available upon request.  
Sherman, K. 2015. Creating and Invasive Plant Management Strategy: A Framework for Ontario Municipalities. Ontario Invasive Plant Council, Peterborough, ON. 38 pp.  
Thorntwaite, C.W. and Mather, J. (1957) Instructions and Tables for Computing Potential Evapotranspiration and the Water Balance. Laboratory of Climatology, 10.

Town of Caledon 2018. Town of Caledon Official Plan. Consolidated April 2018.

Town of Caledon OP (2018) Environmental Policy Area provisions for the Coleraine West Employment Area Land Use Plan (Section 7.15.8(iv));  
Town of Caledon, 2023. Official Plan Amendment 274 (By-law 2023-087). Available online: <https://www.caledon.ca/en/town-services/resources/Business-Planning--Development/Development-Services/Humber-Station-Secondary-Plan/1.-Notice-of-Adoption-OPA-274.pdf>

Town of Caledon, 2024. Official Plan. Available online: <https://www.caledon.ca/en/town-services/official-plan.aspx>

Town of Caledon. 2024. Applications, Licenses and Permits. Available online: <https://www.caledon.ca/en/government/applications-licences-and-permits.aspx#:~:text=You%20will%20need%20a%20fill,or%20store%20or%20remove%20topsoil>

Town of Caledon, 2023. Amendment No. XXX – Humber Station Employment Area Secondary Plan. Available online: <https://www.caledon.ca/en/town-services/resources/Business-Planning--Development/Development-Services/Humber-Station-Secondary-Plan/Revised-June-2024-Draft-Humber-Station-Employment-Area-Secondary-Plan.pdf>

Toronto and Region Conservation Authority (TRCA). 2004. Post-Construction Restoration Guidelines. Available online: [https://trca.ca/app/uploads/2016/02/Post-Construction\\_Restoration\\_Guidelines\\_July\\_2004.pdf](https://trca.ca/app/uploads/2016/02/Post-Construction_Restoration_Guidelines_July_2004.pdf)

Toronto and Region Conservation Authority (TRCA). 2012. Preserving and Restoring Healthy Soil: Best Practices for Urban Construction. Available online: [https://trcaca.s3.ca-central-1.amazonaws.com/app/uploads/2021/10/20103048/preserving\\_and\\_restoring\\_healthy\\_soil\\_trca\\_2012.pdf](https://trcaca.s3.ca-central-1.amazonaws.com/app/uploads/2021/10/20103048/preserving_and_restoring_healthy_soil_trca_2012.pdf)

Toronto and Region Conservation Authority (TRCA). 2019. Erosion and Sediment Control Guideline for Urban Construction. Toronto and Region Conservation Authority, Vaughan, Ontario.

Toronto and Region Conservation Authority (TRCA). 2022. Seed Mix Guideline V.2.0. Available online: [https://trcaca.s3.ca-central-1.amazonaws.com/app/uploads/2022/02/01124117/Seed-Mix-Guidelines-Update\\_January-19-2022.pdf](https://trcaca.s3.ca-central-1.amazonaws.com/app/uploads/2022/02/01124117/Seed-Mix-Guidelines-Update_January-19-2022.pdf)



Toronto and Region Conservation Authority (TRCA). 2023. Guideline for Determining Ecosystem Compensation. Available online: <https://trcaca.s3.ca-central-1.amazonaws.com/app/uploads/2023/08/18123313/TRCA-Ecosystem-Compensation-Guideline-June-2023.pdf>

Toronto and Region Conservation Authority. 2021. Flora Species for Entire TRCA Jurisdiction. Available online: [https://trcaca.s3.ca-central-1.amazonaws.com/app/uploads/2021/07/21084253/2021\\_Flora\\_Ranks\\_\\_Scores.pdf](https://trcaca.s3.ca-central-1.amazonaws.com/app/uploads/2021/07/21084253/2021_Flora_Ranks__Scores.pdf)

U.S. Fish and Wildlife Service and California Invasive Plant Council 2018. Land Manager's Guide to Developing an Invasive Plant Management Plan. Cal-IPC Publication 2018-01. National Wildlife Refuge System, Pacific Southwest Region, Inventory and Monitoring Initiative, Sacramento, CA. California Invasive Plant Council, Berkeley, CA. Available online: [www.cal-ipc.org](http://www.cal-ipc.org) and [data.gov](http://data.gov)

Varga, S., editor. 2005. Distribution and status of the vascular plants of the Greater Toronto Area. Ontario Ministry of Natural Resources, Aurora District. 96 pp.






# Appendix A

---

## Figures





Project 1901485

**NOTES:**  
 1. Coordinate System: NAD 1983 UTM Zone 17N.  
 2. Base features produced under license with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2024.


- Legend**
- Study Area
  - 120 m Adjacent Lands
  - Railway
  - Municipal Boundary, Lower/Single Tier
  - Municipal Boundary, Upper Tier
  - Watercourse
  - Waterbody
  - Wooded Area

Humber Station, Town of Caledon, ON

Figure 1  
 Location of Study Area

0 500 m  
 1:30,000





**ELC Legend**

CUM1-1	Dry Moist Old Field Meadow
CUP	Coniferous Plantation
CUT	Cultural Thicket
CUT1	Mineral Cultural Thicket
CUT1-1	Sumac Cultural Thicket
CUT1-7*	Buckthorn Cultural Thicket
FOD	Deciduous Forest
FOD7-6*	Fresh-Moist Manitoba Maple Lowland Deciduous Forest
FOD8-3*	Fresh-Moist Basswood Deciduous Forest
MAM	Meadow Marsh
MAM2	Mineral Meadow Marsh
MAM2-2	Reed-canary Grass Mineral Meadow Marsh
MAM2-10	Forb Mineral Meadow Marsh
MAS	Shallow Marsh
MAS2	Mineral Shallow Marsh
MAS2-1	Cattail Mineral Shallow Marsh
OA	Open Aquatic
SAS1-1	Pondweed Submerged Shallow Aquatic
SWT2-2	Willow Mineral Thicket Swamp
AG	Agricultural
DIST	Disturbed
H	Hedgerow
IND	Industrial
Lawn	Lawn
Pond	Pond
RES	Residential

\*Not included in Southern Ontario ELC Field Guide.

	Study Area
	Participating Properties
	Non-participating Properties
	Ecological Land Classification
	Watercourse (MNR LIO)
	Significant Woodland
	Terrestrial Crayfish Chimney Observation
	Significant Wetland (GEI Consultants Ltd.)
	Unevaluated/Assumed Significant Wetland (GEI Consultants Ltd.)

**HDF Management Recommendations**

	Conservation
	Protection
	Mitigation
	No Management Required
	Conservation - Non-participating Ownership
	Protection - Non-participating Ownership
	Mitigation - Non-participating Ownership

**NOTES:**

1. Coordinate System: NAD 1983 UTM Zone 17N.
2. Base features produced under license with the Ontario Ministry of Natural Resources and Forestry © Queen's Printer for Ontario, 2024.
3. Orthoimagery © First Base Solutions, 2024. Imagery taken in 2022.


Project 1901485

Humber Station, Town of Caledon, ON

**Figure 2**  
Pre-development Natural Heritage System (Existing Conditions)

0 100 Meters  
**1:8,000**





**ELC Legend**

- CUM1-1 Dry Moist Old Field Meadow
- CUP Coniferous Plantation
- CUT Cultural Thicket
- CUT1 Mineral Cultural Thicket
- CUT1-1 Sumac Cultural Thicket
- CUT1-7\* Buckthorn Cultural Thicket
- FOD Deciduous Forest
- FOD7-6\* Fresh-Moist Manitoba Maple Lowland Deciduous Forest
- FOD8-3\* Fresh-Moist Basswood Deciduous Forest
- MAM Meadow Marsh
- MAM2 Mineral Meadow Marsh
- MAM2-2 Reed-canary Grass Mineral Meadow Marsh
- MAM2-10 Forb Mineral Meadow Marsh
- MAS Shallow Marsh
- MAS2 Mineral Shallow Marsh
- MAS2-1 Cattail Mineral Shallow Marsh
- OA Open Aquatic
- SAS1-1 Pondweed Submerged Shallow Aquatic
- SWT2-2 Willow Mineral Thicket Swamp
  
- AG Agricultural
- DIST Disturbed
- H Hedgerow
- IND Industrial
- Lawn Lawn
- Pond Pond
- RES Residential

\*Not included in Southern Ontario ELC Field Guide.


- Study Area
- Participating Properties
- Non-participating Properties
- Watercourse/Drainage
- Creek Bank (Staked on October 19, 2021 by TRCA and GEI)
- Dripline (Staked on October 19, 2021 by TRCA and GEI)
- Hydrologic Edge of Wetland (Staked on October 19, 2021 by TRCA and GEI)
- Wetland (Staked on October 19, 2021 by TRCA and GEI)
- Stable Top of Slope (GEI) + 10 m
- Unconfined Meanderbelt (GEI) + 10 m
- Top of Bank Estimate Based on LIDAR + 10 m
- Conceptual Wetland Compensation + 10 m
- Wetland + 10 m
- Wetland + 30 m
- Wetland (off-site) + 30 m
- Regional Floodline + 10 m
- 100 Year Floodline + 10 m
- Top of Bank + 10 m (Staked on October 19, 2021 by TRCA and GEI)
- Significant Woodland + 10 m
- Warm Water Fish Habitat + 15 m
- Preliminary Natural Heritage System Limit
- Preliminary Natural Heritage System Limit (Potential for Realignment)
- Proposed Woodland Removal (0.34 ha)
- Proposed Woodland Compensation (0.35 ha)
- Proposed Wetland Removal (0.38 ha)
- Proposed Wetland Buffer Removal (0.15 ha)
- Proposed Wetland Buffer Compensation (0.15 ha)
- Drainage Realignment Wetland Enhancement Area (0.58 ha)
- Wetland Compensation Area 1 (0.08 ha)
- Wetland Compensation Area 2 (0.39 ha)
- Wetland Compensation Area 3 (0.35 ha)
- Approximate Highway 413 Alignment
- 100 Year Floodline
- Regional Floodline
- Conceptual Drainage Feature Realignment
- Site Plan
- Grading
- Proposed SWM Facility
- Proposed Storm Tank
- Proposed Storm Sewers

Humber Station, Town of Caledon, ON

Figure 3  
Preliminary Natural Heritage System

0 100 Meters





Orthoimagery: First Base Solutions, 2023. Imagery taken in 2021.

CLIENT  
**HUMBER STATION  
 VILLAGE LANDOWNERS  
 GROUP INC.**  
 C/O DELTA URBAN INC.  
 8800 DUFFERIN ST., 104 VAUGHAN, ON  
 L4K 0C5

COPYRIGHT  
 This drawing has been prepared solely for the intended use, thus any reproduction or distribution for any purpose other than authorized by Arcadis is prohibited. Written dimensions shall have precedence over scaled dimensions. Contractors shall verify and be responsible for all dimensions and conditions on the job and Arcadis shall be informed of any variations from the dimensions and conditions shown on the drawing. Shop drawings shall be submitted to Arcadis for general conformance before proceeding with fabrication.

Arcadis Professional Services (Canada) Inc.  
 is a part of Arcadis

ISSUES

No.	DESCRIPTION	DATE
1	ISSUED FOR REVIEW	2024-08-30
2	ISSUED FOR REVIEW	2024-09-06



CONSULTANTS

SEAL




PROJECT  
**CEISMP - Phase 1  
 Characterization / Existing  
 Condition & Baseline Inventory**  
 Bolton, ON

PROJECT NO:  
 141438

DRAWN BY: NL	CHECKED BY: SD
PROJECT MGR: SD	APPROVED BY: SD


SHEET TITLE  
**ZONE OF INFLUENCE**

SHEET NUMBER <b>Figure 5</b>	ISSUE <b>1</b>
---------------------------------	-------------------



**LEGEND:**

BH18 MONITORING WELL	-260.00- GROUNDWATER CONTOUR
WATER WELL SUPPLY	WETLAND
STUDY AREA	ZONE OF INFLUENCE (1889m)
ROADS	
WATERCOURSE	













File Location: \\c:\arcadis\group\com\j\101\141438\_Humber\17.0\_Production\7.07\_Spatial\_Design\Humber Station - Outstanding Materials Phase 207\_CAD\141438-HumberStation-OutstandingMaterialsPhase2\_Fig5-201.dwg Last Saved: August 29, 2024, by nastasia.lauzon Plotted: Friday, September 6, 2024 11:35:35 AM by Nastasia Lauzon  
 SCALE CHECK: 1/16



# SCHEDULE C8 HUMBER STATION EMPLOYMENT AREA LAND USE PLAN

## Legend

-  Bolton Settlement Area
-  Secondary Plan Area
-  Environmental Policy Areas
-  Prestige Employment
-  General Employment
-  Conceptual Road Network
-  Highway 413 Transportation Corridor
-  Highway 413 Focus Area



Base Data Source: Town of Caledon




# Appendix B

---

Fluvial










**REACH 1 - PROPOSED PLAN VIEW**

SCALE 1:500



- GENERAL NOTES:**
1. ALL DIMENSIONS ARE IN METRES OR MILLIMETRES, UNLESS OTHERWISE NOTED.
  2. ACTIVITIES WITHIN THE WATERCOURSE SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION TIMING WINDOW IDENTIFIED BY THE MECP AND CONSERVATION AUTHORITY.
  3. ALL IN-WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN THE DRY DURING THE TIMING WINDOW SPECIFIED.
  4. CONSTRUCTION SHALL NOT COMMENCE UNTIL ALL UTILITY LOCATIONS HAVE BEEN REVIEWED AND ALL PERMITS AND APPROVALS HAVE BEEN RECEIVED BY THE CONTRACT ADMINISTRATOR.
  5. A DETAILED ESC PLAN, INTENDED TO PREVENT ENTRY OF SEDIMENT INTO THE WATER COURSE AND NATURAL AREAS, SHALL BE PREPARED PRIOR TO CONSTRUCTION AND ADHERED TO FOR THE DURATION OF CONSTRUCTION. ANY DEVIATION FROM APPROVED PLANS MUST BE DESIGNED BY A QUALIFIED PROFESSIONAL.



**REACH 1 - PROPOSED PROFILE**

SCALE 1:500

No.	DATE	ISSUE/REVISION	INITIAL
1	8/28/24	CONCEPT - 30% DESIGN	LM


HUMBER STATION VILLAGE LOG

CHANNEL RE-ALIGNMENT

PLANVIEW AND PROFILE - REACH 1





DESIGNED BY: LM	DATE: AUGUST 2024	CHECKED BY: AS
DRAWN BY: AS / LM	PROJECT No. 1901485	DRAWING No. G-01
SCALE: 1:500		



**REACH 2 - PROPOSED PLAN VIEW**  
SCALE 1:750

- GENERAL NOTES:**
1. ALL DIMENSIONS ARE IN METRES OR MILLIMETRES, UNLESS OTHERWISE NOTED.
  2. ACTIVITIES WITHIN THE WATERCOURSE SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION TIMING WINDOW IDENTIFIED BY THE MECP AND CONSERVATION AUTHORITY.
  3. ALL IN-WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN THE DRY DURING THE TIMING WINDOW SPECIFIED.
  4. CONSTRUCTION SHALL NOT COMMENCE UNTIL ALL UTILITY LOCATIONS HAVE BEEN REVIEWED AND ALL PERMITS AND APPROVALS HAVE BEEN RECEIVED BY THE CONTRACT ADMINISTRATOR.
  5. A DETAILED ESC PLAN, INTENDED TO PREVENT ENTRY OF SEDIMENT INTO THE WATER COURSE AND NATURAL AREAS, SHALL BE PREPARED PRIOR TO CONSTRUCTION AND ADHERED TO FOR THE DURATION OF CONSTRUCTION. ANY DEVIATION FROM APPROVED PLANS MUST BE DESIGNED BY A QUALIFIED PROFESSIONAL.





**REACH 2 - PROPOSED PROFILE**  
SCALE 1:750

No.	DATE	ISSUE/REVISION	INITIAL
1	8/28/24	CONCEPT - 30% DESIGN	LM


HUMBER STATION VILLAGE LOG  
CHANNEL RE-ALIGNMENT  
PLANVIEW AND PROFILE REACH 2




DESIGNED BY: LM	DATE: AUGUST 2024	CHECKED BY: AS
DRAWN BY: AS / LM	PROJECT No. 1901485	DRAWING No. G-02
SCALE: 1:750		



- GENERAL NOTES:**
1. ALL DIMENSIONS ARE IN METRES OR MILLIMETRES, UNLESS OTHERWISE NOTED.
  2. ACTIVITIES WITHIN THE WATERCOURSE SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION TIMING WINDOW IDENTIFIED BY THE MECP AND CONSERVATION AUTHORITY.
  3. ALL IN-WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN THE DRY DURING THE TIMING WINDOW SPECIFIED.
  4. CONSTRUCTION SHALL NOT COMMENCE UNTIL ALL UTILITY LOCATIONS HAVE BEEN REVIEWED AND ALL PERMITS AND APPROVALS HAVE BEEN RECEIVED BY THE CONTRACT ADMINISTRATOR.
  5. A DETAILED ESC PLAN, INTENDED TO PREVENT ENTRY OF SEDIMENT INTO THE WATER COURSE AND NATURAL AREAS, SHALL BE PREPARED PRIOR TO CONSTRUCTION AND ADHERED TO FOR THE DURATION OF CONSTRUCTION. ANY DEVIATION FROM APPROVED PLANS MUST BE DESIGNED BY A QUALIFIED PROFESSIONAL.



**REACH 3 - PROPOSED PLAN VIEW: PART 1**  
SCALE 1:750



No.	DATE	ISSUE/REVISION	INITIAL
1	8/28/24	CONCEPT - 30% DESIGN	LM

HUMBER STATION VILLAGE LOG


CHANNEL RE-ALIGNMENT

PLANVIEW AND PROFILE REACH 3: PART 1




DESIGNED BY: LM	DATE: AUGUST 2024	CHECKED BY: AS
DRAWN BY: AS / LM	PROJECT No. 1901485	DRAWING No. G-03
SCALE: 1:750		


**REACH 3 - PROPOSED PROFILE: PART 1**  
SCALE 1:750




**REACH 3 - PROPOSED PLAN VIEW: PART 2**  
SCALE 1:750



**REACH 3 - PROPOSED PROFILE: PART 2**  
SCALE 1:750



- GENERAL NOTES:**
1. ALL DIMENSIONS ARE IN METRES OR MILLIMETRES, UNLESS OTHERWISE NOTED.
  2. ACTIVITIES WITHIN THE WATERCOURSE SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION TIMING WINDOW IDENTIFIED BY THE MECP AND CONSERVATION AUTHORITY.
  3. ALL IN-WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN THE DRY DURING THE TIMING WINDOW SPECIFIED.
  4. CONSTRUCTION SHALL NOT COMMENCE UNTIL ALL UTILITY LOCATIONS HAVE BEEN REVIEWED AND ALL PERMITS AND APPROVALS HAVE BEEN RECEIVED BY THE CONTRACT ADMINISTRATOR.
  5. A DETAILED ESC PLAN, INTENDED TO PREVENT ENTRY OF SEDIMENT INTO THE WATER COURSE AND NATURAL AREAS, SHALL BE PREPARED PRIOR TO CONSTRUCTION AND ADHERED TO FOR THE DURATION OF CONSTRUCTION. ANY DEVIATION FROM APPROVED PLANS MUST BE DESIGNED BY A QUALIFIED PROFESSIONAL.




No.	DATE	ISSUE/REVISION	INITIAL
1	8/28/24	CONCEPT - 30% DESIGN	LM


HUMBER STATION VILLAGE LOG  
CHANNEL RE-ALIGNMENT  
PLANVIEW AND PROFILE REACH 3: PART 1




DESIGNED BY: LM	DATE: AUGUST 2024	CHECKED BY: AS
DRAWN BY: AS / LM	PROJECT No. 1901485	DRAWING No. G-04
SCALE: 1:750		




**COMPENSATION WETLAND AREA 2**  
SCALE 1:500



**COMPENSATION WETLAND AREA 3**  
SCALE 1:500



- GENERAL NOTES:**
1. ALL DIMENSIONS ARE IN METRES OR MILLIMETRES, UNLESS OTHERWISE NOTED.
  2. ACTIVITIES WITHIN THE WATERCOURSE SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION TIMING WINDOW IDENTIFIED BY THE MECP AND CONSERVATION AUTHORITY.
  3. ALL IN-WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN THE DRY DURING THE TIMING WINDOW SPECIFIED.
  4. CONSTRUCTION SHALL NOT COMMENCE UNTIL ALL UTILITY LOCATIONS HAVE BEEN REVIEWED AND ALL PERMITS AND APPROVALS HAVE BEEN RECEIVED BY THE CONTRACT ADMINISTRATOR.
  5. A DETAILED ESC PLAN, INTENDED TO PREVENT ENTRY OF SEDIMENT INTO THE WATER COURSE AND NATURAL AREAS, SHALL BE PREPARED PRIOR TO CONSTRUCTION AND ADHERED TO FOR THE DURATION OF CONSTRUCTION. ANY DEVIATION FROM APPROVED PLANS MUST BE DESIGNED BY A QUALIFIED PROFESSIONAL.



No.	DATE	ISSUE/REVISION	INITIAL
1	8/28/24	CONCEPT - 30% DESIGN	LM







HUMBER STATION VILLAGE LOG

WETLAND PLANS

PLANVIEW



DESIGNED BY: LM	DATE: AUGUST 2024	CHECKED BY: AS
DRAWN BY: AS / LM	PROJECT No. 1901485	DRAWING No. G-05
SCALE: 1:500		



GENERAL NOTES:

- ALL DIMENSIONS ARE IN METRES OR MILLIMETRES, UNLESS OTHERWISE NOTED.
- ACTIVITIES WITHIN THE WATERCOURSE SHALL BE IN ACCORDANCE WITH THE CONSTRUCTION TIMING WINDOW IDENTIFIED BY THE MECP AND CONSERVATION AUTHORITY.
- ALL IN-WATER AND NEAR WATER WORKS WILL BE CONDUCTED IN THE DRY DURING THE TIMING WINDOW SPECIFIED.
- CONSTRUCTION SHALL NOT COMMENCE UNTIL ALL PERMITS AND APPROVALS HAVE BEEN RECEIVED BY THE CONTRACT ADMINISTRATOR.
- A DETAILED ESC PLAN, INTENDED TO PREVENT ENTRY OF SEDIMENT INTO THE WATER COURSE AND NATURAL AREAS, SHALL BE PREPARED PRIOR TO CONSTRUCTION AND ADHERED TO FOR THE DURATION OF CONSTRUCTION. ANY DEVIATION FROM APPROVED PLANS MUST BE DESIGNED BY A QUALIFIED PROFESSIONAL.

HUMBER STATION VILLAGE LOG

CHANNEL RE-ALIGNMENT

CHANNEL DETAILS



DESIGNED BY: LM DATE: AUGUST 2024 CHECKED BY: AS  
 DRAWN BY: AS/LM PROJECT No. 1901485 DRAWING No. G-06  
 SCALE: NTS

# Appendix C

---

## Tables



**Table 9. Natural Heritage System Implementation (Phasing) Plan**

Unique ID	Action	Feasible Months	Comments
1	Install Erosion and Sediment Control Measures	Post-spring freshet to hard frost	Where vegetation removal is required for ESC measure installation, follow vegetation removal window for ESC installation
2	Install Tree Protection Fencing as per Arborist Report	Post-spring freshet to hard frost	
3	Tree removal and stockpile for reuse	December 1 to March 14	Bat exit survey if tree removal planned between March 15 and Nov. 30; Includes ALL trees within the Subject Lands including CUT1/CUW1, and Arborist trees identified for removal
4	Botanist flags shrubs for live cutting within MAM, MAS and FOD8-3	Within 1 month of planned live cutting	
5	Botanist flags area for wetland soil salvage within MAM and MAS	Late August to Early September	Survey when invasive species can be identified and excluded; Salvage soil from areas with <25% woody cover
6	Remove, stockpile, and cover salvaged wetland soil as per TRCA healthy soil guidelines	Mid-September to hard frost	
7	Take live cuttings and prepare for storage	October, November, March	when plants are dormant
8	Take live cuttings and install in retained NHS or created NHS	October, November, March	when plants are dormant
9	Vegetation (grass, flower, shrub) removal within development footprint, excluding to be removed wetlands	Sept. 16 to March 31	Nest sweep surveys if veg. removal planned between April 1st and Sept. 15; Includes CUT1/CUW1 planned for removal
10	Interim condition Compensation Wetland C catchment fine grading and stabilization (seed mix)	Post spring freshet to June 30; September 1 to Nov. 15	Compensation Wetland C is hydrologically supported by precipitation and an industrial roof. Interim conditions (i.e., direct overland flow through vegetated field to wetland) is expected
11	Interim condition retained wetland catchment grading and stabilization (seed mix)	Post spring freshet to June 30; September 1 to Nov. 15	
12	Amphibian and turtle wildlife rescue and relocation from within to be removed wetlands	Amphibian and reptile salvage to occur between March 15 - April 30; August 1 - October 1	Once wildlife rescue is completed, vegetation removal and rough grading (wetland removal) occur. Should vegetation removal occur ahead of September 15 then nest sweep surveys are required
13	Vegetation removal of wetlands identified in Environmental Impact Study for removal. Interim compensation wetland conditions need to be in place (stabilized (100% vegetative cover) interim wetland catchment and compensation wetland)	Sept. 16 to March 31	Nest sweep surveys if veg. removal planned between April 1st and Sept. 15
14	Rough grading of proposed drain realignment (HDF-3) and Compensation Wetlands 1, 2 and 3	Post spring freshet to hard frost	Implement stabilization measures should fine grading and plant installation not follow rough grading
15	Rough grading of compensation woodland	Post spring freshet to hard frost	Implement stabilization measures should fine grading and plant installation not follow rough grading
16	Site preparation (till, topsoil quality and depth), fine grading and stabilization (100% vegetative cover from interim seed mix) of proposed drain realignment (HDF-3) and Compensation Wetlands 1, 2 and 3	May, June, Sept., Oct., Nov.	To occur immediately following site preparation
17	Site preparation (till, topsoil quality and depth), fine grading and plant installation of compensation woodland	May, June, Sept., Oct., Nov.	
18	Site preparation (till, topsoil quality and depth) and planting of NHS buffer planting area	May, June, Sept., Oct., Nov.	
19	Connect industrial roof to Compensation Wetland 3	May, June, Sept., Oct., Nov.	



Unique ID	Action	Feasible Months	Comments
20	Ultimate Compensation Wetland 3 Site Preparation (i.e., mow interim condition vegetation; check topsoil depth and quality)	May, August, Sept.	Occurs prior to "turning on" ultimate hydrological input source. Ecologists advise engineers when planted conditions are suitable to "turn on" water source.
21	Ultimate Compensation Wetland 3 Plant Installation (i.e., seed mix, potted material)	May, June, Sept., Oct., Nov.	Occurs prior to "turning on" ultimate hydrological input source. Ecologists advise engineers when planted conditions are suitable to "turn on" water source.
22	Fine Grading and Plant Installation of Stormwater Management Pond Outfall	May, June, Sept., Oct., Nov.	
23	In water works for road culverts installation	July 1 to September 14	Follow Redside Dace in-water works window

**Table 10. Wildlife Construction Windows by Permitting Authority**

<b>Wildlife Window</b>	<b>Regulating Agency</b>	<b>Regulation/Policy</b>	<b>Construction Window</b>	<b>If Construction proposed within wildlife window?</b>
Species at Risk Bats	Ministry of Environment Conservation and Parks	Ontario Endangered Species Act	Tree removal from December 1 through March 14	Bat Exit Surveys Required
Migratory Birds	Environment and Climate Change Canada	Migratory Bird Convention Act	Vegetation removal (grass, flowers, shrubs) September 16 to March 31	Nest Sweep Surveys Required
In Water Works for Fisheries	Department of Fisheries and Oceans/Ministry of Environment Conservation and Parks	Fisheries Act, Ontario Endangered Species Act	Drainage Feature Realignment - July 1 to September 15	Requires formal application to DFO and MECP for authorized extension (typically the latest extension given is Sept. 30)
Amphibian and Reptile Wildlife Salvage and Relocation	Ministry of Natural Resources and Forestry	Scientific Collectors Permit; Wildlife Care Committee Application	Amphibian and reptile salvage to occur between March 15 - April 30; August 1 - October 1	MNRF would consider extending window to October 31, depending on weather and site conditions

**Table 11. Long Term Monitoring Plan and Comprehensive Adaptive Management Plan**

Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
<b>Landscape Architecture</b>									
Compliance Monitoring	Plant Warranty Monitoring	Inspect each installed plant and applied seed mix for healthy growth	Inspect immediately following installation and in Spring of the following year for healthy growth	N/A	YES, during 2-year plant warranty period  Retained Natural Heritage System Buffers  Compensation Wetland 1, 2, and 3  Compensation Woodland  Realigned Drainage Feature	N/A	Poor health/dead of individual planted stock  Poor germination coverage of cover crop and/or native seed mix	Ecologist/ Landscape architect to advise landscape contractor on need for them to do soil amendments ahead of replanting Soil amendments – landscape contractor to carry out requested amendments including conduct topsoil and/or hydric soil testing, add/remove topsoil or hydric soil or mulch, tilling ahead of replanting Plant stock – Replace with like, or substitution subject to approval by project ecologist of landscape architect Reapply a cover crop and/or native seed mix. Cover crop and/or native seed mix may differ than that originally seeded, upon direction of the landscape architect/ecologist	Awarded Landscape Contractor to cover cost of vegetation replacements  Land Developer to cover costs of ecological/ landscape architecture contract administration and landscape contractor progress payments
<b>Erosion and Sediment Control</b>									
To verify that all ESC measures have been implemented and are functioning according to specifications and requirements	In accordance with the Erosion and Sediment Control Guidelines for Urban Construction (TRCA 2019) erosion and sediment control inspections will be conducted to monitor the condition of the ESC measures, dewatering activities, and the receiving water body downstream of the work area, concurrently along	Prevent sediment from construction activities from entering natural heritage features and functions	On a weekly basis; and After every major rainfall event (greater than 10 mm	N/A	On a weekly basis; and After every major rainfall event (greater than 10 mm	N/A	ESC measures observed to be insufficient measure for preventing sediment from entering NHS	Change ESC measures (i.e., type of silt fencing or number of silt fences) and increase frequency of monitoring until it is demonstrated that revised ESC measures in place are suitable for conditions present	Land Developer Group

Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
	with the construction inspections. The inspections will identify the potential of the release of debris, sediment, and other deleterious substances into the wetland, and will serve to inform any mitigation measures to be implemented								
<b>Terrestrial</b>									
Ecological Land Classification	Document the vegetation communities in the final year pre-assumption	Increase in vegetation communities in post-NHS over pre-development NHS	Spring, summer, and fall vegetation surveys to be completed. Vegetation communities to be mapped and refined with each seasonal assessment. Vegetation community types identified using protocol outlined in Ecological Land Classification (ELC) for Southern Ontario (Lee et al. 1998). ELC completed to the finest level of resolution feasible. Species names generally follow nomenclature from the Database of Vascular Plants of Canada (Brouillet et al. 2010+).  The provincial status of all plant species and vegetation communities to be based on NHIC (in year study occurs). Identification of potentially sensitive native plant species is based on their assigned coefficient of conservatism (CC) value, as determined by Oldham et al. (1995). This CC value, ranging from 0 (low) to 10 (high), is based on a species tolerance of disturbance and fidelity to a specific natural habitat.	Document existing NHS ELC	N/A	Final year of post-construction monitoring ahead of assumption  Post-Development NHS to be surveyed	N/A	N/A	Land Developer Group

Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
			Species with a CC value of 9 or 10 generally exhibit a high degree of fidelity to a narrow range of habitat parameters.						
Floristic Quality	Documents the floristic diversity within the post-construction NHS (new NHS). The quality of which will be gauged using the Floristic Quality Index (FQI). Additional floristic metrics such as wetness index and weediness index will also be calculated. These data can help identify vegetative responses to growing conditions, such as hydrology.  Outlines what Category 1 invasive species are present (if any) and their general abundance and distribution. Based on species, abundance and distribution complete a risk assessment to evaluate whether to manage the species. Where management is planned, identify the management method as per the Ontario Invasive Plant Council Best Management practices.	FQI target	Summer and fall botanical inventories will be completed. Calculate floristic metrics within each ecosite or vegetation community, such as FQI, weediness index, and wetness index.  Pre-development NHS method – Field survey a georeferenced 50 x 50 m grid with each square assigned a unique identifier. The abundance level of each of the observed Category 1 invasive species is documented based on vegetation cover within each square using the ELC abundance categories (Lee et al. 1998): rare (0-10%), occasional (10-50%), abundant (50-90%), and dominant (>90%). Category 1 invasives to be assessed, as per “Invasive Exotic Species Ranking for Southern Ontario” (Urban Forest Associates Inc. 2002).	Pre-Development Natural Heritage System  Identify priority NHS construction areas to monitor and manage, where a) retained NHS is adjacent and contains Category 1 invasive species and b) early detection and rapid response for Category 1 invasives within the “under construction” NHS	N/A	Post-Development Natural Heritage System  Continued monitoring and management within constructed NHS of Priority Category 1 invasive species until assumption.	N/A	N/A	Land Developer Group
Invasive Species		Category 1 Invasive Species (i.e., Common Buckthorn, European Reed)			Under Construction NHS priority Category 1 invasive monitoring and management. Where planting occurs conduct early detect and rapid response for priority Category 1 invasive species.		Through monitoring identify priority Category 1 invasive species	Manage identified priority Category 1 invasive species	Land Developer Group

Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
Retained Wetland Ecohydrology	Wetland Hydroperiod (monthly)	Hydroperiod suitable for wetland vegetation	Piezometers with continuous data loggers to record surface water and groundwater position. Barologger on site	During ice-free period: continuous datalogger measurements with monthly inspection and manual reading	During ice-free period: continuous datalogger measurements with monthly inspection and manual reading	During ice-free period: continuous datalogger measurements with monthly inspection and manual reading.	1a) Pre-construction hydroperiod is not provided during construction or post-development  1b) SAS1-1 standing water levels < 60 cm	Assess if hydrological inputs are affected by climate (e.g., high ET/temp/low precipitation)  If not, identify opportunities for reducing/increasing hydrological inputs (e.g., rooftop, LID) to restore wetland hydrology	
Created Wetland Ecohydrology	1) Wetland Hydroperiod (monthly)  2) Hydrological input/output  3) Wetland vegetation cover (50% or greater)	1) Hydroperiod suitable for wetland vegetation  2) Is volume of water entering and exiting wetland as modeled  3) Wetland vegetation covers majority of the wetland area	1) Piezometers with continuous data loggers to record surface water and groundwater position. Barologger on site  2) Water Level Loggers at Wetland Inlet and Outlet of Wetland Compensation Area 1, 2 and 3  3) visual assessment of wetland vegetation cover per 2022 OWES protocol	N/A  N/A  N/A	N/A  N/A  N/A	1) During ice-free period: continuous datalogger measurements with monthly inspection and manual reading  2) During ice-free period: datalogger measurements with monthly inspection and manual reading  3) Annual in July	1) Hydrological inputs and/or storage not suitable for wetland establishment  2) Modeled flow volumes at inlet and outlet not provided and wetland vegetation not present within compensation wetland  3) Wetland vegetation cover < 50%	Assess if hydrological inputs are affected by climate (e.g., high ET/temp/low precipitation)  Assess if there are issues with the constructed wetland itself through hydrological and soil quality investigation  Identify where water is going, assess need for topographic revisions in wetland, supplement hydrological inputs (e.g., rooftop, LID), and/or soil quality improvements	Land Developer Group (until assumption)
Breeding Amphibians	Call count surveys	Maintain or increase amphibian biodiversity post-development over pre-	Survey protocols to be based on the 'Marsh Monitoring Program' (Bird Studies Canada (BSC) 2014).  Survey station locations (retained NHS and new NHS)	Document pre-development anuran biodiversity in existing NHS	N/A	In the final year prior to assumption conduct breeding amphibian surveys. Compare pre-post development NHS to ascertain if amphibian	N/A	N/A	Land Developer Group

Long Term Monitoring Plan						Comprehensive Adaptive Management Plan			
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
		development conditions	to be conducted at night within the appropriate timing window from approximately 30 minutes after sunset until midnight. Each station to be surveyed three times (once in April, once in May and once in June) during optimal weather conditions (low wind levels, no heavy rain). Minimum night air temperatures at time of survey of 5°C, 10°C and 17°C were applied to each of the respective survey periods. Surveys to be conducted at least 15 days apart. All calls heard within a survey station are to be recorded, as well as any call observations outside of the survey station, including on adjacent lands.			biodiversity maintained or increased post-development			
Species at Risk and Significant Wildlife Habitat (Bird)	Breeding Bird Survey	Bank Swallow (SAR) Eastern Wood Pewee (SWH)	Breeding bird surveys should be conducted following protocols set forth by the Ontario Breeding Bird Atlas (Cadman et al., 1998; Cadman et al., 2007). Surveys should be conducted between dawn and five hours after dawn with suitable wind conditions, no thick fog or precipitation (Cadman et al., 2007). Point count stations should be located adjacent to candidate/confirmed habitat within the Study Area. Surveys should be conducted at least 10 days apart.	Bank Swallow foraging habitat documented within non-participating lands and Wetland D1. Habitat to be retained.  Confirmed Eastern Wood Pewee SWH documented within FOD located on non-participating lands. Habitat to be retained	N/A	In final year ahead of assumption document location of retained NHS and created NHS Species at Risk and Significant Wildlife Bird Habitat	N/A	N/A	Land Developer Group

Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
Significant Wildlife Habitat (Insects)	Insect Visual Occurrence Surveys	Monarch & Yellow-banded Bumblebee	Insect surveys, including Monarchs and yellow-banded bumblebee, do not currently have a set protocol in Ontario. Species detection is dependent on repeated visits during the appropriate flight times for a given species in suitable habitat. Three visual surveys/ area searches could be conducted within all suitable habitats present within the Study Area, with an emphasis on areas with common milkweed for monarch surveys. Surveys should take place between mid-morning and noon or late afternoon to sunset with mostly sunny skies, suitable low wind conditions, no thick fog or precipitation. Temperatures should be between 22°C and 30°C such that insect activity is optimal. Survey periods should take place: <ul style="list-style-type: none"> <li>• Early May to mid-June;</li> <li>• Mid-June to mid-July; and</li> <li>• Late July to late August.</li> </ul>	Habitat documented in old field/meadows associated with Clarkway Drive Tributary valley. Habitat to be retained.	N/A	In final year ahead of assumption document location of retained NHS and created NHS Significant Wildlife Habitat (Insects)	N/A	N/A	Land Developer Group
Significant Wildlife Habitat (Invertebrates)	1) Terrestrial Crayfish Chimney Surveys	Terrestrial Crayfish	1) Targeted visual crayfish chimney surveys should be completed for retained wetlands with confirmed habitat (wetland C1 and D1) and Wetland Compensation Area 2. Ideal timing for chimney surveys is April to Mid-June when the water table is highest. Chimney clusters and/or individual chimneys should be recorded with a GPS-unit to note geographic distribution	Documented confirmed habitat within wetland C1 and D1	N/A	In final year ahead of assumption document location habitat within retained NHS and created NHS Significant Wildlife Habitat (Invertebrates)	N/A	N/A	Land Developer Group



Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
	2) Terrestrial Crayfish Occurrence Surveys		2) Visual occurrences of terrestrial crayfish are less common, however at least two nocturnal surveys during spring rainfall are recommended; these should be targeted towards the retained portion of wetland C1 and Wetland Compensation Area 2						
Significant Wildlife Habitat (Mammals)*		Bat Maternity Colonies	<p>Surveys should be completed following MECP survey guidelines as outlined in “Species at Risk Bats Note” (MECP, 2022), Bats and Bat Habitats: Guidelines for Wind Power Projects (MNR, 2011) and “Maternity Roost Surveys (Forests/Woodlands) (MECP, 2022)</p> <p>Habitat assessments should be completed during the leaf-off period. All trees and snags greater than or equal to 10 cm diameter-at-breast height (DBH) should be visually inspected using binoculars to document any cavities, leaf clusters, and loose or peeling bark that may or may not be present along the trunk or large branches. Areas with ≥10 cavities/ha determined to provide the greatest potential bat maternity roost habitat in accordance with MNRF guidelines; these areas should then be targeted for acoustic monitoring. Bat acoustic monitoring devices should be deployed for at least 10 consecutive nights in June. These recordings should then be analyzed by experts to identify species occurrence</p>	Candidate bat maternity colony habitat is assumed within non-participating woodland communities. Candidate habitat to be retained	N/A	In final year ahead of assumption document location of retained NHS and created NHS Significant Wildlife Habitat (Mammals)	N/A	N/A	*Non-Participating Landowner

Long Term Monitoring Plan						Comprehensive Adaptive Management Plan			
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
<b>Aquatic (Fisheries)</b>									
Redside Dace contributing habitat	<p>1) Erosion and Sediment Control (see ESC Section above)</p> <p>2) Stormwater Management Facility Performance Monitoring (see Stormwater Management Pond and Surface Water Quality Sections below)</p> <p>3) Warranty monitoring of vegetation (see Landscape Architecture Compliance Monitoring Section above)</p>	Contributing Redside Dace Habitat (Includes: Realigned Drainage Feature and Compensation Wetlands 1, 2 and 3)	<p>1) See Erosion and Sediment Control Section above</p> <p>2) See Stormwater Management Pond and Surface Water Quality Sections below</p> <p>3) See Landscape Architecture Compliance Monitoring Section above</p>		<p>1) See ESC Section above (On a weekly basis; and after every major rainfall event (greater than 10 mm)). Additional monitoring should include visual</p> <p>2) N/A</p> <p>3) Realigned Drainage Feature and Compensation Wetlands 1, 2 and 3 during 2-year plant warranty period</p>	<p>1) N/A</p> <p>2) All SWM Ponds and Realigned Drainage Feature – beginning one year post-installation (see Stormwater Management Pond and Surface Water Quality Sections below)</p> <p>3) N/A</p>	<p>1) ESC measures observed to be insufficient measure for preventing sediment from entering NHS</p> <p>2) Any exceedance of the relevant criteria (TSS and/or temperature thresholds).</p> <p>3) Poor health/dead of individual planted stock; Poor germination coverage of cover crop and/or native seed mix</p>	<p>1) Change ESC measures (i.e., type of silt fencing or number of silt fences) and increase frequency of monitoring until it is demonstrated that revised ESC measures in place are suitable for conditions present</p> <p>2) All discharge of pumped water into the natural environment should be halted, and other options for pre-treatment system should be explored</p> <p>3) Ecologist/ Landscape architect to advise landscape contractor on need for them to do soil amendments ahead of replanting Soil amendments – landscape contractor to carry out requested amendments including conduct topsoil and/or hydric soil testing, add/remove topsoil or hydric soil or mulch, tilling ahead of replanting Plant stock – Replace with like, or substitution subject to approval by project ecologist of landscape architect Reapply a cover crop and/or native seed</p>	Land Developer Group

Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
								mix. Cover crop and/or native seed mix may differ than that originally seeded, upon direction of the landscape architect/ecologist	
Warmwater Fish Habitat	<p>1) Aquatic Habitat Assessment (AHA)</p> <p>2) Warranty monitoring of vegetation (see Landscape Architecture Compliance Monitoring above)</p> <p>3) Surface water quality (general chemistry and temperature: see Water Resources Surface Water Quality section below)</p>	Warm water fish habitat	<p>1) AHA: Visual assessment and mapping throughout drainage feature realignment to evaluate fish habitat conditions. The assessment should note:</p> <ul style="list-style-type: none"> <li>• Hydrology (e.g. flowing or standing water);</li> <li>• General watercourse morphology;</li> <li>• Wetted width and depth (at time of survey);</li> <li>• Any instream habitat (e.g. woody debris, aquatic vegetation, undercut banks);</li> <li>• Presence of obstructions to fish movement (e.g. culverts, debris dams); and</li> <li>• Riparian habitat.</li> </ul> <p>2) See Landscape Architecture Compliance Monitoring Section above</p> <p>3) See Water Resources Surface Water Quality section below)</p>	Warmwater fish habitat was identified within HDF-3 and the Clarkway Drive Tributary.	<p>1) N/A</p> <p>2) Realigned Drainage Feature riparian vegetation monitoring during 2-year plant warranty period</p> <p>3) See Water Resources Surface Water Quality section below)</p>	<p>1) Annually for 3 years post-construction for the realigned Drainage Feature</p> <p>2) N/A</p> <p>3) Continuous logging at 15-minute intervals during years 1, 3, and 5.</p>	<p>1) N/A</p> <p>2) Poor health/dead of individual planted stock; Poor germination coverage of cover crop and/or native seed mix</p> <p>3) Significant changes compared to baseline conditions</p>	<p>1) N/A</p> <p>2) Replace poor stock with like, or substitution subject to approval by project ecologist of landscape architect, or, reapply a cover crop and/or native seed mix to ensure riparian vegetation is established</p> <p>3) Design remediation to minimize quality and thermal impacts (i.e., flow rates, permanent pool depth) and explore additional LID</p>	Land Developer Group

Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
								implementation where feasible.	
<b>Fluvial Geomorphology</b>									
Evaluate performance of realigned drainage feature	Channel cross section	Channel adjustments	Survey of channel cross sections at minimum of 2 runs and 2 pools	N/A	N/A	Annually for 3 years post-construction	Adjustments of greater than 20% of the cross-sectional area	Review flows within the channel and identify need for mitigation or adjustments to the implemented design	Land Developer Group
	Lateral migration	Channel adjustments	Erosion pins installed at the outer bank of	N/A	N/A	Annually for 3 years post-construction	Adjustments of greater than 20 cm per year	Review whether erosion is localized or a site-wide issue, and identify need for mitigation or adjustments to the implemented design	Land Developer Group
	Substrate composition	Channel adjustments	Pebble counts	N/A	N/A	Annually for 3 years post-construction	Significant grain size adjustments (such as increase in siltation or loss of coarse materials)	Review flows within the stream and identify whether mitigation is required.	Land Developer Group
<b>Water Resources</b>									
<b>Surface Water Quantity</b>									
Evaluate potential changes in flow conditions.	Flow characteristics	Will be evaluated in relation to baseline conditions, with no specific targets set.	Flow measurements at designated locations.	Every 4 months for 1 to 2 years before construction begins.	Every 4 months until the buildout is complete.	Every 4 months at designated locations during years 1, 3, and 5.	Substantial flow changes to HDF or watercourses compared to the baseline.	Apply the findings to future developments to minimize long-term impact. Adjust outflows as needed and where feasible using storm flow rate controls.	Land Developer Group
<b>Water Resources Surface Water Quality</b>									
Evaluate potential changes in water quality	Water Quality: General Chemistry	Will be evaluated in relation to baseline conditions, with no specific targets set.	Surface water sampling at designated locations. Quality parameters of dissolved oxygen, pH, water hardness, turbidity, total suspended solids and total phosphorus	Every 4 months for 1 to 2 years before construction begins.	Every 4 months until the construction is complete.	Every 4 months at designated locations during years 1, 3, and 5.	Significant changes in water chemistry in comparison to baseline	Apply the findings to future developments to minimize long-term impact. Adjust SWM to minimize quality and thermal impacts (ie: flow rates, permanent pool depth, additional LID implementation where feasible)	Land Developer Group

Long Term Monitoring Plan							Comprehensive Adaptive Management Plan		
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
	Water Quality: Temperature	Will be evaluated in relation to baseline conditions, with no specific targets set.	Temperature loggers at designated locations.	Continuous logging at 15-minute intervals for 1 to 2 years before construction begins.	Continuous logging at 15-minute intervals for 1 to 2 years until the construction is complete.	Continuous logging at 15-minute intervals during years 1, 3, and 5.	Significant changes in water temperature compared to baseline condition	Adjust SWM as feasible for thermal impacts (ie: flow rates, permanent pool depth, additional LID implementation where feasible)	Land Developer Group
<b>Stormwater Management Ponds</b>									
Evaluate if SWM criteria meet TRCA, MOE and Town of Caledon Standards	SWM Pond Water Levels and flow	Verify if target release rates are met based on SWM Report	Flow loggers downstream of control structures to monitor flows	NA	Continuous logging at 15-minute intervals for 1 to 2 years before construction begins.	Continuous logging at 15-minute intervals during years 1, 3, and 5	Significant changes in flows in comparison to Town, TRCA and MOE criteria	Adjust SWM as feasible, modify control structure	Land Developer Group
Evaluate if SWM criteria meet TRCA, MOE and Town of Caledon Standards	SWM Pond water outflow temperature	General reference for water chemistry and temperature	Temperature loggers at pond outlet	NA	Continuous logging at 15-minute intervals for 1 to 2 years before construction begins.	Continuous logging at 15-minute intervals during years 1, 3, and 5	Significant changes in temperature in comparison to Town, TRCA and MOE criteria	Adjust SWM as feasible for quality impacts (ie: flow rates, permanent pool depth, additional LID implementation where feasible)	Land Developer Group
Evaluate if SWM criteria meet TRCA, MOE and Town of Caledon Standards	SWM Pond Water Quality chemistry and temperature at outlet and inlet	General reference for water chemistry	Water quality parameters of dissolved oxygen, pH, water hardness, turbidity, total suspended solids and total phosphorus to be evaluated at the inlet and outlet	NA	Every 4 months until the construction is complete.	Every 4 months at designated locations during years 1, 3, and 5.	Notable differences in water chemistry compared to the criteria set by the Town, TRCA, and MOE	Adjust SWM as feasible for thermal impacts (i.e., flow rates, permanent pool depth, additional LID implementation where feasible)	Land Developer Group
<b>Site Groundwater Quantity</b>									
Confirm if Site water levels have been impacted by construction.	On-Site Groundwater levels (available on-site monitoring wells, existing off-alignment monitoring wells)	Groundwater levels decline 5 m below observed seasonally low recorded baseline groundwater level in select off-alignment monitoring wells (near perimeter of ZOI) during construction. Specific trigger	Manual measurements and continuous interval readings at select off-alignment monitoring well locations during preconstruction. Dataloggers employed at select locations in relation to George Bolton Parkway and Street A-2 during construction and for 1 year following construction.	Seasonal groundwater monitoring data (4 / year) should continue to be collected until the start of construction	Weekly manual measurements for the first month, and then biweekly to monthly afterwards. Continuous interval reading (1-hour interval) using a pressure transducer	Quarterly manual water level measurements and continuous interval readings at select on-site wells (that have not been destroyed during construction), and selected off-alignment wells for a period of 1-year following construction	<b>During Construction:</b> Water level decline > 5m during construction  <b>Post- construction trigger:</b> Water levels do not return to 80% + of baseline	<b>During construction:</b> Confirm the magnitude of drawdown and assess for potential groundwater receptors that may be affected. Additional waterproofing / water reduction construction methodology and techniques to be implemented in subsequent	Land Developer Group

Long Term Monitoring Plan						Comprehensive Adaptive Management Plan			
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
		levels to be determined once additional studies of the sanitary services has been completed.						<p>construction activities. Continue monitoring to confirm the recovery of drawdown beyond the expected ZOI.</p> <p><b>Post-Construction:</b> Upon completion of the 1-year post-construction monitoring program, an assessment will be made by to determine whether conditions have returned to acceptable levels and/or further monitoring is required, in consultation with the CA. Continue monitoring if deemed appropriate. Additional recharge facilities can be contemplated if required in consultation with the CA.</p>	
<b>Off-Site Groundwater Quantity and Quality</b>									
Confirm if off-site water levels have been impacted by construction	Groundwater Level and Quality (nutrient and microbiology parameters) at nearby participating private wells	Upon receipt of resident complaint, or if Groundwater quality exceeds the ODWS and has degraded when compared to baseline quality as appropriate and to be determined on a case-by-case basis	Complete door-to-door private well survey within the estimated ZOI. Conduct a visual inspection of the well and photograph the well. Manual water level measurements using water level tape. Laboratory analysis for various parameters (nitrate, nitrite, phosphate, metals, total coliform, fecal coliforms, <i>E.Coli.</i> ).	Once prior to construction	Quarterly monitoring or upon receipt of resident complaint	Quarterly manual water level measurements and continuous interval readings (datalogger to be installed) in impacted private wells for a period of 1-year following construction. At the end of the earthworks, a water level measurement and a water sample will again be collected from each of the monitored water supply wells to confirm the post-development water quality.	<p>Upon receipt of resident complaint</p> <p><b>During construction</b> - Confirm well water level and/or quality impacts below usable levels. Confirm whether construction activities are the cause of impacts to the water wells</p> <p><b>Post-construction</b> - Groundwater levels do not return to an</p>	<p><b>During construction</b> - If impacts are identified, provide temporary water supply to impacted residents</p> <p><b>Post construction</b> - Upon completion of the 1-year post-construction monitoring program, an assessment will be made the consultant to determine whether conditions have</p>	Land Developer Group

Long Term Monitoring Plan						Comprehensive Adaptive Management Plan			
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
		The results of the well monitoring program will be documented and a copy made available to the Region					acceptable level for domestic use. Groundwater quality exceeds the ODWS and has degraded when compared to baseline quality as appropriate and to be determined on a case-by-case basis	returned to acceptable levels and/or further monitoring is required, in consultation with the Region and / or CA. Land Developer Group to determine solution to supplement impacted residents' potable water supply as necessary	
<b>Site Groundwater Quality</b>									
Characterization of on-site groundwater quality and confirm that groundwater quality has not been degraded because of construction	General chemistry indicators: including field chemistry parameters (temperature, pH, DO, turbidity) Select Provincial Water Quality Objectives (PWQO) (applicable metals, O&G) and Peel Storm Sewer Use By-Law municipal sewer use by law, if applicable	No net degradation of groundwater quality relative to relevant criteria	Sampling from select monitoring wells. Laboratory samples to be stored in ice-chilled coolers and submitted to a CALA-certified laboratory under chain-of-custody documentation on same day as sample collection. Field chemistry parameters (temperature, pH, DO, turbidity) collected with appropriate calibrated instrument(s) (e.g., YSI). Sampling to occur from same well each monitoring year, except in cases where wells have been decommissioned due to construction	Once prior to construction	Semi-annually	Yearly water quality sampling at selected on-site wells (that have not been destroyed during construction), and off-alignment wells (TBD) for a period of 1-year following construction	<b>During Construction:</b> Exceedance of PWQO or sewer bylaw when compared to baseline condition  <b>Following Construction:</b> Exceedance of Sewer Use bylaw PWQO when compared to applicable baseline conditions	<b>During Construction:</b> If changes in groundwater quality are identified through monitoring, determine if pumping or other construction activity is the cause of change in groundwater quality. Determine if impacts to groundwater receptors may occur. Add appropriate pre-treatment technology to the discharge system.  <b>Following Construction:</b> Confirm whether construction activities are the cause of impacts to the water wells. Continue monitoring if deemed appropriate.	Land Developer Group

Long Term Monitoring Plan						Comprehensive Adaptive Management Plan			
Performance Measure Indicator(s)/ Objective(s)	Monitoring Parameter	Monitoring Target(s) or Threshold(s)	Methods/ Protocols/ Analyses	Monitoring Frequency and Duration			Trigger	Response	Responsibilities for Monitoring and Cost*
				Pre-Construction	During Construction	Post-Construction (Performance)			
<b>Dewatering Effluent Water Quality</b>									
Confirm dewatering effluent water quality and confirm that quality is suitable for discharge to intended receiver.	TSS, DO, pH, EC, turbidity, metals, VOCs, PHCs and inorganics	Groundwater quality meets criteria relevant for intended receiver	Unfiltered sampling from a controlled dewatering discharge port to be collected for field and laboratory analysis. Field chemistry parameters (temperature, pH, DO, turbidity) collected with appropriate calibrated instrument(s) (e.g., YSI). Laboratory samples to be stored in ice-chilled coolers and submitted to a CALA-certified laboratory under chain-of-custody documentation on same day as sample collection.	Not applicable	During active dewatering, Daily monitoring: TSS Weekly monitoring: DO, pH, EC, turbidity, metals, VOCs, PHCs and inorganics  Dewater to a well-vegetated area, 30 m away from a watercourse or wetland, and use a filter bag along with appropriate sediment barrier, such as silt socks/coir logs/straw bales	Not applicable	<b>During Construction:</b> pH between 6.5 and 8.5 Turbidity – 8 NTU (TSS at 25 mg/L). Any exceedance of the relevant criteria.	<b>During Construction:</b> All discharge of pumped water into the natural environment should be halted, and other options for pre-treatment system should be explored	Land Developer Group